
FUGRO NATIONAL INC LONG BEACH CA F/6 8/7 MX SITING INVESTIGATION. GEOTECHNICAL EVALUATION. AGGREGATE RES--ETC(U) JUN 80 F04704-80-(C-0006 FN-TR-37-A NL AD-A112 406 UNCLASSIFIED NL 1 - 2




# MX SITING INVESTIGATION GEOTECHNICAL EVALUATION

AD A 112466

AGGREGATE RESOURCES STUDIES
DRY LAKE VALLEY
MULESHOE VALLEY
DELAMAR VALLEY
PAHROC VALLEY
NEVADA

PREPARED FOR BALLISTIC MISSILE OFFICE (BMO) NORTON AIR FORCE BASE, CALIFORNIA



PHOTOGRAPH THIS SHEET
S LEVEL INVENTORY
LEVEL INVENTORY  FN-TR-37-A  DOCUMENT IDENTIFICATION
This document has been approved for public release and sale; its distribution is unlimited.  DISTRIBUTION STATEMENT
ACCESSION FOR
NTIS GRAAI DTIC TAB UNANNOUNCED JUSTIFICATION  BY  BY
DISTRIBUTION / AVAILABILITY CODES  DIST AVAILAND/OR SPECIAL  COPY INSPECTED  Original contains color plates: All DTIC reproducts
DISTRIBUTION STAMP
82 03 13 107
DATE RECEIVED IN DTIC
PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDA-2
DTIC FORM 70A DOCUMENT PROCESSING SHE

**OCT 79** 

ı	REPORT DO MENTATION	READ INSTRUCTIONS BEFORE COMPLETING FORM		
	1. REPORT NUMBER		3. RECIPIENT'S CATALOG NUMBER	
	FNTR 37a			
	4. TITLE (and Subtitle) AGG regate Reso	urces Studies	5. TYPE OF REPORT & PERIOD COVERED	
	pry Lake while, mulesh	De.	C	
	belomar + Pahrocc	, ,	6. PERFORMING ONG. REPORT HUMBER	
	Neu	. /1	FN TR 372	
-	7. AUTHOR(a)		B. CONTRACT OR GRANT NUMBER(s)	
,	Fugro Notimal,	Inc.	F04704-80-C-0006	
	9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
į	Ertec Western Inc. Germerly P.O. BOX 7765	tradio National		
	Long Beach Ca 90807		64312 F -	
	11 CONTROLLING OFFICE NAME AND ADDRESS		12. REPORT DATE	
į	5pace and Missile System	ue conce	6500 80	
ı		(50,050)	13. NUMBER OF PAGES	
<b>i</b> . {	No CHOY AFIS CO 92409 14. MONITORING AGENCY NAME & ADDRESS(II different	t from Controlling Office)	15. SECURITY CLASS. (of this report)	
	·		unclassified	
1				
			154 DECLASSIFICATION/DOWNGRADING SCHEDULE	
	16. DISTRIBUTION STATEMENT (of this Report)			
		•		
	Distribution Ur	11imited		
1				
i	17. DISTRIBUTION STATEMENT (of the abstract entered	in Block 20, if different from	n Report)	
Ì	, , , <del>, , , , , , , , , , , , , , , , </del>			
	Distribution U	nlimited		
	18. SUPPLEMENTARY NOTES			
1				
ı				
1	19. KEY WORDS (Continue on reverse side if necessary and Seo log	d identify by block number)	, Potentia gregate	
1	GEOTOF OSCIOLARIOS	Je	and the	
ı	SOUTCES, Longies	A	anto Colicho	
1	Shouties physiography	<i>או רבירי ע</i> ץ		
	20. ABSTRACT (Continue on reverse side if necessary and	I identify by black number)		
ì		yormutica	on the above	
ł		Sitahi	litu of basin-lill	
١	Valley's in Jocation	1, 20 11 9121	do do hase	
	ock sources for co	increte M	1000x-pase	
ı	mostruction materia	Us. The	a Trype of aggregate	
1	reconcer are delinente	0 in the	for rolling,	
Į	donas donas me	Assalaha	di egoragold	
ī	DO FORM 1479		V1 U	

## AGGREGATE RESOURCES STUDIES

DRY LAKE VALLEY MULESHOE VALLEY DELAMAR VALLEY PAHROC VALLEY

NEVADA

## Prepared for:

U.S. Department of the Air Force Ballistic Missile Office (BMO) Norton Air Force Base, California 92409

Prepared by:

Fugro National, Inc. 3777 Long Beach Boulevard Long Beach, California 90807

6 June 1980

Franc Hattenal, INC.

#### **FOREWORD**

This report was prepared for the Department of the Air Force Ballistic Missile Office (BMO) in compliance with Contract No. F04704-80-C-0006, CDRL Item No. 004A2. It presents the results of Valley-Specific Aggregate Resources studies within and adjacent to selected areas in Utah and Nevada that are under consideration for siting the MX system.

This volume contains the results of the aggregate resources studies in Dry Lake, Muleshoe, Delamar, and Pahroc valleys. It is the first of several Valley-Specific Aggregate Resources investigations which will be prepared as separate volumes. Results of this report are presented as text, appendices, and two drawings.

# TABLE OF CONTENTS

		<u> </u>	age
FORE	WORD		i
EXEC	UTIVE	SUMMARY	1
1.0	INTR	ODUCTION	4
	1.1	Study Area	4
	1.2	Background	4
	1.3	Objectives	6
	1.4	Scope	6
2.0	STUD	Y APPROACH	9
	2.1	Existing Data	9
	2.2	Supplemental Fugro National Data	9
	2.3	Data Analysis	11
	2.4	Presentation of Results	11
	2.5	Preliminary Classification of Potential	
		Aggregate Sources	14
3.0	GEOL	OGIC SETTING	17
	3.1	Physiography	17
	3.2	Location and Description of Geologic Units	17
	3.2	3.2.1 Rock Units	19
		3.2.1.1 Quartzite - Qtz	19
		3.2.1.2 Limestone - Ls	20
		3.2.1.3 Dolomite - Do	20
		3.2.1.4 Carbonate Rocks	
		Undifferentiated - Cau	21
		3.2.1.5 Sedimentary Rocks	
		Undifferentiated - Su	21
		3.2.1.6 Basalt - Vb	22
		3.2.1.7 Volcanic Rocks	
		Undifferentiated - Vu	22
		3.2.2 Basin-Fill Units	22
		3.2.2.1 Older Lacustrine Deposits - Aol .	23
		3.2.2.2 Alluvial Fan Deposits - Aaf	23
		3.2.2.3 Stream Channel and Terrace	
		Deposits - Aal	24
		3.2.2.4 Alluvial Deposits	
		Undifferentiated - Au	24
4.0	POTE	NTIAL AGGREGATE SOURCES	26
	4.1	Basin-Fill Sources	27
		4.1.1 Coarse Aggregate	27

# TABLE OF CONTENTS (Cont.)

									Page
			4.1.1.1				e Concre		
				Aggr	egate a	and Roa	d-Base M	(ateria)	
							• • • • • •		27
			4.1.1.2				Concret		
				Aggr	egate/	Potenti	ally Sui	itable	
							1 Source		
							• • • • • • •		29
			4.1.1.3		able Co	oncrete	Aggrega	ate or	
							1 Source		
							• • • • • • •		
		4.1.2	Fine Agg						29
			4.1.2.1						
							d-Base M		
							• • • • • •		29
			4.1.2.2						
							ally Sui		
							l Source		
							• • • • • • •		30
			4.1.2.3						
							l Source		
							• • • • • • •		
	4.2		Rock So						32
		4.2.1	Potentia						
							rces - C		32
		4.2.2	Possibly						
							Base Mat		
									35
		4.2.3	Unsuitab						
			Base M	aterial	Source	es - Cla	ass III	• • • • • •	36
5.0	CONCI	LUSIONS	• • • • • • •	• • • • • •	• • • • • •	• • • • • •	• • • • • • •	•••••	37
		D		D/11 1					22
	5.1		ial Basin						
			Coarse A						
	E 2		Fine Agg						
	5.2	Potenti	al Crush	ed Rock	Aggre	gate So	urces	•••••	38
6.0	RECO	MENDATI	ONS FOR	FUTURE S	STUDIES	<u> </u>	• • • • • • •		40
BTBI.	TOGRA	ЭНУ							41
	, ,								74

# TABLE OF CONTENTS (Cont.)

		Page
	LIST OF APPENDICES	
APPENDIX		
A	Fugro National Field Station and Supplementary Test Data and Existing Test Data Summary Tables Dry Lake, Muleshoe, Delamar, and Pahroc Valleys	-
В	Summary of Caliche Development	
С	Unified Soil Classification System	
D	Dry Lake, Muleshoe, Delamar, and Pahroc Valleys	
-	Study Area Photographs	
E	Fugro National Geologic Unit Cross Reference	
	LIST OF TABLES	
Table Number		
1	Aggregate Tests - Dry Lake, Muleshoe, Delamar, and	đ
	Pahroc Valleys, Aggregate Resources Study	. 12
2	Preliminary Aggregate Classification System, Valley-Specific Aggregate Resources Study	. 15
	LIST OF FIGURES	
Figure Number		
1	Aggregate Resources Studies Dry Lake, Muleshoe,	
	Delamar, and Pahroc Valleys, Nevada	
2	Utah-Nevada Regional Aggregate Studies	. 7
	LIST OF DRAWINGS	
Drawing Number		
1		ocket
2	Delamar, and Pahroc Valleys at a Aggregate Resources Map Dry Lake, Muleshoe, of Roberts Delamar, and Pahroc Valleys	ena eport

## EXECUTIVE SUMMARY

This report contains the Valley-Specific Aggregate Resources Study (VSARS) evaluation for Dry Lake, Muleshoe, Delamar, and Pahroc valleys in Nevada. It is the first in a series of reports that contain valley-specific aggregate information on the location and suitability of basin-fill and rock sources for concrete and road-base construction materials. Field reconnaissance and limited laboratory testing, existing data from the State of Nevada Department of Highways, previous regional aggregate investigation, and ongoing Verification studies provide the basis for the findings presented.

A classification system based on aggregate type and potential use was developed to rank the suitability of all basin-fill and rock aggregate sources. Four aggregate types have been designated; coarse, fine, and coarse and fine (multiple) aggregates derived from basin-fill sources and crushed rock aggregates derived from rock sources. Each aggregate type was then classified using the following definitions:

- Class I Potentially suitable concrete aggregate and road-base material source.
- Class II Possibly unsuitable concrete aggregate/potentially suitable road-base material source.
- Class III Unsuitable concrete aggregate or road-base material source.

Decisions on assigning a particular aggregate source to one of the three classes were determined from Fugro National and existing laboratory aggregate tests performed as part of this

- France MATIGNAL, INC.

study (abrasion resistance, soundness, and alkali reactivity), and to a lesser degree, field visual observations.

Emphasis in this study was placed on the identification of Class I basin-fill, coarse aggregate. These deposits are considered to be the primary sources of concrete and road-base construction materials. Results of the study are presented on a 1:125,000 scale aggregate resources map (Drawing 2) and are summarized as follows:

- Coarse Aggregate Three major Class I coarse aggregate basin-fill deposits were located in the four-valley study area.
  - a. An extensive alluvial fan complex west of the Bristol, Highland, and Burnt Springs ranges in east-central Dry Lake Valley.
  - b. Older lacustrine deposits west of Pahroc Valley (Pahranagat Valley).
  - c. Limited alluvial fan deposits bordering the Delamar Mountains in east-central Delamar Valley.

Potential Class II coarse aggregate sources are widespread and extensive in the study area. Although boundaries of specific deposits could not be delineated, they are typically located within alluvial fans flanking Class I and/or Class II rock sources.

2. <u>Fine Aggregate</u> - Most coarse aggregate basin-fill sources are also potential multiple sources (coarse and fine) that will supply varying quantiti s of fine aggregate either from

FURRO MATIONAL, INC.

the natural deposit or during processing. However, specific alluvial fan deposits, predominantly comprised of Class I fine aggregate material were identified in northern Muleshoe Valley flanking the Bristol Range and Dutch John Mountain.

3. Crushed Rock - Abundant Class I crushed rock sources surround the study area. Unnamed upper Cambrian and Pennsylvanian and the Highland Peak and Guilmette formations are widespread carbonate rocks (limestone and dolomite) that compose most Class I sources. Individual units or combinations of these units are most extensive in the northern portions of Muleshoe Valley and eastern Dry Lake and Delamar valleys. The useability of any of these rock units as sources of crushed rock aggregate will depend on their location and accessibility within the study area and minability.

Additional aggregate testing and field investigations will be required to further refine the lateral and vertical extents of classification boundaries and define exact physical and chemical characteristics of a particular deposit or rock source within the valley.

**funko** HATIOHAL, ING.

#### 1.0 INTRODUCTION

#### 1.1 STUDY AREA

This report presents the results of the Valley-Specific Aggregate Resources Study completed for Dry Lake, Muleshoe, Delamar, and Pahroc valleys (Figure 1). Located in the central portion of Lincoln County, Nevada, the area is elongate in shape with north-south trending alluvial basins flanked by carbonate and volcanic rock mountain ranges. Cave, White River, and Pahranagat valleys border the site on the west and Lake and Pine valleys form the eastern boundary.

U.S. Highway 93 provides access along the eastern boundary and to the central study region. State Highway 38, an improved gravel road, provides access to the western border. A network of unpaved roads and 4-wheel-drive trails crisscross the site area (Drawing 1).

The valleys are mainly comprised of desert rangeland. Several active mining operations are located in the Bristol and Highland ranges. The towns of Pioche and Caliente, Nevada, lie just within the east-central border of the Valley-Specific area and are serviced by the mainline of the Union Pacific Railroad from Salt Lake City, Utah, to Las Vegas, Nevada.

#### 1.2 BACKGROUND

The MX aggregate program began in 1977 with the investigation of Department of Defense (DOD) and Bureau of Land Management (BLM) lands in California, Nevada, Arizona, New Mexico, and Texas

TUGRO NATIONAL, INC.

(FN-TR-20D). Refinement of the MX siting area added portions of Utah and Nevada that were not studied in the initial Aggregate Resources Evaluation Investigation (AREI). This additional area (Figure 2), defined as the Utah Aggregate Resources Study area (UARSA), was evaluated in Fall 1979 and a second general aggregate resources report (FN-TR-34) was submitted on 3 March 1980. Both general aggregate investigations were designed to provide regional information of the general location, quality, and quantity of aggregates that could be used in the construction of the MX system.

Subsequent to the general studies, Valley-Specific Aggregate Resources Studies (VSARS) were developed in FY 79 to provide more detailed information on potential aggregate sources in specified valley areas.

#### 1.3 OBJECTIVES


The primary objective of the VSARS program is to classify on a valley basis, basin-fill deposits and rock for suitability as concrete and road base construction materials. The VSARS format is designed to select and present the locations of the most acceptable aggregate sources for preliminary construction planning and follow-on, detailed aggregate investigations.

#### 1.4 SCOPE

The scope of this investigation required office and field investigations and included the following:

 Collection and analysis of available existing data on the quality and quantity of potential concrete aggregate and road base material sources. American Society

France MATTERIAL ME



of Testing and Materials (ASTM) standards and Standard Specifications for Public Works Construction (SSPWC) were used to evaluate quality.

- (2) Aerial and ground reconnaissance of all identified potential aggregate sources in the valley area, with more detailed investigation and sample collection of likely basin-fill (coarse and fine aggregates) and rock (crushed rock aggregates) construction material sources.
- (3) Laboratory testing to supplement available existing data and to provide detailed information to assist in determining the suitability of specific basin-fill or rock deposits as construction material sources within the valley area.
- (4) Development and application of an aggregate classification system (Section 2.5) that emphasizes aggregate type (coarse, fine, or crushed rock) and potential construction use (concrete and/or road base).

#### 2.0 STUDY APPROACH

#### 2.1 EXISTING DATA

Collection of existing test data from available sources was an important factor in the VSARS program. The principal source of existing data directly pertaining to aggregate construction materials was the State of Nevada Department of Highways (Appendix A). The majority of this information is related to the use of aggregate material for asphaltic concrete, base course in road construction, or ballast material. However, many of the suitability tests for these types of construction materials are similar to those for concrete and were applicable to this investigation (Appendix A).

### 2.2 SUPPLEMENTAL FUGRO NATIONAL DATA

Supplemental Fugro National data were obtain from: (1) field data and supplementary test data compiled during the general aggregate resources study (FN-TR-20D), (2) Dry Lake Valley Verification study (FN-TR-27-DL-I and II), (3) Muleshoe, Delamar, and Pahroc Verification studies (in progress), and (4) the current Valley-Specific Aggregate Resources Study (Appendix A).

Although the primary objective of the initial, general aggregate study was directed toward developing regional evaluations and rankings of all potential aggregate sources, the 20 data points included in the Valley-Specific study area (Drawing 1) also supplied specific aggregate information. These 20 stops contained three 100-pound samples collected for limited laboratory testing (Appendix A).

TURNO HATIBHAL, INC.

Verification geologic maps were an initial source of information on the type and extent of basin-fill units within specific valley area. In addition, Verification study data included information from 25 trench locations distributed thoughout the study area (Drawing 1). Depths of the selected trenches ranged from 5 to 18 feet. While the Verification studies are not specifically designed to generate aggregate data, the sampling techniques and testing procedures (Appendix A) are applicable to the aggregate evaluation.

The VSARS program required aerial and ground reconnaissance of the study area to collect additional information to verify conditions determined during the data review. Included in the 63 field station data stops was the collection of 23 samples for laboratory testing. Potential coarse and fine aggregate basinfill samples were collected by channel sampling stream cuts or occassional man-made exposures. Potential crushed rock aggregate samples were obtained from exposures of fresh or slightly weathered material whenever possible. The weight of the samples collected range between 100 and 150 pounds. Hand samples, which generally did not exceed 5 pounds in weight, were collected for office analyses.

Identification of basin-fill materials in all field studies followed ASTM D2488-69 Description of Soils (Visual-Manual Procedure), and the Unified Soil Classification System (Appendix C). Rock identifications followed procedures described in the

Quarterly of the Colorado School of Mines and Standard Investigative Nomenclature of Constituents of Natural Mineral Aggreques (ASTM C294-69).

#### 2.3 DATA ANALYSIS

Geologic and engineering criteria were used in the evaluation of potential aggregate sources within the study area. This was supplemented by laboratory analysis of selected samples during the Valley-Specific aggregate testing program (Table 1). Coarse aggregate is defined as plus 0.185 inch (4.699 mm) fine gravel to boulders basin-fill material. Fine aggregate is defined as minus 0.375 inch (9.52 mm) coarse to fine sand basin-fill material. While all laboratory tests supplied definitive information, the soundness, abrasion, and alkali reactivity results were considered the most critical in determining the use and acceptability of a potential aggregate source.

#### 2.4 PRESENTATION OF RESULTS

Results of the study are presented in textual form, tables, two 1:125,000 scale maps, and appendices. Drawing 1 presents the location of the 121 existing test data and supplemental Fugro data sites within the study area. Drawing 2 presents the location of all VSARS laboratory sample sites and all potential basin-fill and rock aggregate sources within the valley area. In addition, these potential aggregate sources are classified according to proposed aggregate use and type (Section 2.5).

fuene Hattenal, ING.

ASTM TEST	SAMPLE TYPE AND NUMBER OF TESTS			
MSIM 1231	COARSE	FINE	ROCK	
ASTM C-88; SOUNDNESS BY USE OF MAGNESIUM SULFATE	11	10	6	
ASTM C-131; RESISTANCE TO ABRASION By USE OF THE LOS ANGELES MACHINE	12		8	
ASTM C-136; SIEVE ANALYSIS	12	10		
ASTM C-289; POTENTIAL REACTIVITY OF AGGREGATES (CHEMICAL METHOD)	3	2	3	
ASTM C-127 AND C-128; SPECIFIC GRAVITY AND ABSORPTION	9	3	5	

AGGREGATE TESTS
DRY LAKE, MULESHOE, DELAMAR,
AND PAHROC VALLEYS
AGGREGATE RESOURCES STUDIES, NEVADA

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE - BMO

TABLE

JERO NATIONAL INC.

Geologic unit symbols utilized in Drawing 2 relate to standard geological nomenclature whenever possible. Undifferentiated basin-fill and rock units were established primarily to accomodate accuracy of data and map scale and may contain deposits which could supply significant quantities of high quality materials. A conversion table to relate these geologic symbols to Fugro geologic unit nomenclature is contained in Appendix E.

All contacts which represent distinct boundaries between geologic units are shown as solid lines in Drawing 2. are dashed where the depicted data were extrapolated beyond the limits of the source data or where accuracy of the data may be questionable. Local small deposits of one geologic unit may be found in close association with a larger deposit of a different Due to the reconnaissance level of the field geologic unit. investigation or scale limitations, these smaller deposits could not be depicted on the aggregate resources map and have been combined with the more prevalent material. Similarly, potential aggregate source classifications are preliminary and may contain lesser amounts of material of another use or type. Therefore, all classification lines are dashed and delimit the best aggregate evaluations possible at this level of investigation. In cases of highly variable rock or basin-fill units and limited aggregate tests, boundaries could not be drawn and information is presented as point data on Drawing 2.

Appendices contain tables summarizing the basic data collected during Fugro National's supplemental field investigations, the

frame NATIONAL, INC

results of Fugro National's supplemental testing programs, and existing test data gathered from various outside sources (Appendix A), an explanation of caliche development (Appendix B), the Unified Soil Classification System (Appendix C), photographs of typical aggregate sources within the study area (Appendix D), and a geologic unit cross reference table (Appendix E).

## 2.5 PRELIMINARY CLASSIFICATION OF POTENTIAL AGGREGATE SOURCES

A system was developed to preliminarily classify all potential aggregate sources in the study area. This classification is designed to present the best potential sources of coarse, fine, coarse and fine (multiple source), and crushed rock aggregate types within a Valley-Specific area (Drawing 2) based on potential aggregate use (Table 2). Concrete aggregate parameters are the principal consideration in this report as materials suitable for use as concrete aggregate are generally acceptable for use as road-base material. Therefore, the three classifications described below were based primarily on results of the abrasion, soundness, and alkali reactivity tests.

- Class I Potentially suitable concrete aggregate and road base material source. Coarse and crushed rock aggregates which either passed abrasion, soundness, and alkali reactivity tests or passed abrasion and soundness tests and were not tested for alkali reactivity; fine aggregates which either passed soundness and alkali reactivity tests or passed soundness tests and were not tested for alkali reactivity.
- Class II Possibly unsuitable concrete aggregate/potentially suitable road-base material source. Coarse, fine, and crushed rock aggregates which either failed the soundness and/or alkali reactivity tests or were classified only by field visual observations or other test data.

**FURRO NATIONAL, INC.** 

AGGREGATE CHARACTERISTIC 1			AGGREGATE USE CLASSIFICATION			
			CLASS I	CLASS II	CLASS III	
ABRASION 1	ABRASION RESISTANCE, PERCENT WEAR <sup>2</sup>			<b>~</b> 50	<b>&gt;</b> 50	
	COARSE AGGREGATE	Na SO <sub>4</sub>	<12	<b>&gt;</b> 12	<b>&gt;</b> 12	
S OUNDNESS,	CORNSE AUGREGATE	Mg SO <sub>4</sub>	< 18	> 18	> 18	
PERCENT LOSS <sup>3</sup>	FINE AGGREGATE	Na SO <sub>4</sub>	< 10	> 10	> 10	
		Mg SO <sub>4</sub>	<b>&lt;</b> 15	<b>&gt;</b> 15	<b>&gt;</b> 15	
POTENTIAL ALKALI REACTIVITY 4			INNOCUOUS TO POTENTIALLY DELETERIOUS	DELETERIOUS	DELETERIOUS	

- 1. AGGREGATE CHARACTERISTIC BASED ON STANDARD TEST RESULTS
- 2. ASTM C131 (500 REVOLUTIONS)
- 3. ASTH CBB (5 CYCLES)
- 4. ASTM C289

PRELIMINARY AGGREGATE CLASSIFICATION SYSTEM VALLEY-SPECIFIC AGGREGATE RESOURCES STUDY

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - BMO

TABLE 2

UBRO MATIONAL INC.

Class III Unsuitable concrete aggregate or road base material source. Coarse and crushed rock aggregates which failed abrasion test and were excluded from further testing. Fine, and rarely, coarse aggregates composed of significant amounts of clay- and silt-sized particles.

Sources not specifically identified as Class I, II, or III from the three critical test results or clay- and silt-sized particle content, are designated as Class II sources. All classifications are preliminary with additional field reconnaissance, testing, and case history studies needed to confirm adequacy, delimit areal boundaries, and define exact physical and chemical characteristics.

The following publications/sources were used in defining the three use classifications:

- (1) ASTM C33-74A Standard Specifications for Concrete Aggregate,
- (2) SSPWC Part II Construction Sections 200-1.1, 1.4, 1.5, and 1.7,
- (3) Literature applicable to concrete aggregates,
- (4) Industrial producers of concrete aggregates, and
- (5) Consultants in the field of concrete aggregates.

## 3.0 GEOLOGIC SETTING

## 3.1 PHYSIOGRAPHY

The study area lies entirely within the Basin and Range physiographic province. Primary physiographic features are controlled by block faulting which has produced the uplifted mountains and down-dropped alluvial filled basins characteristic of this region. Mountain ranges and valley basins generally trend north-south. Elevations within the valley range from about 6400 feet (1950 m) at the northern end of the study area to approximately 4400 feet (1340 m) near the southern terminus. Nine mountain ranges bound the valley basin areas. the Schell Creek, North Pahroc, Hiko, and South Pahroc ranges on the west and the Fairview, Bristol, Ely Springs, Highland, Burnt Springs, Chief, and Delamar ranges on the east (Drawing 2). Topographic relief between mountain ridges and basins is generally greatest along the northern and eastern valley margins and ranges from 1000 to 4000 feet (305 to 1220 m). Drainage is essentially closed within Dry Lake and Delamar valleys, whereas, open drainage characterizes Muleshoe and Pahroc valleys.

## 3.2 LOCATION AND DESCRIPTION OF GEOLOGIC UNITS

Paleozoic, Mesozoic, and Cenozoic rocks are found in bedrock highs and mountains within and adjacent to the study area (Drawing 2). Paleozoic sediments consist predominantly of massively to thinly bedded limestones and dolomites with interbedded sandstones, shales, and quartzites. These sediments are located across the entire Valley-Specific area, and where not

**TURRO HATIONAL, INC** 

exposed in bedrock highs, underlie younger geologic units. Unconformably overlying Paleozoic rocks within the site region are Mesozoic deposits consisting predominantly of undifferentiated volcanic and intravolcanic sedimentary rocks principally composed of pyroclastics, mud flows, and breccias of andesitic composition.

Cenozoic rocks uncomformably overlie Paleozoic and Mesozoic units. These rocks consist of Tertiary intrusives, volcanics, and Quaternary alluvial sediments. Tertiary volcanic rocks are composed predominantly of a pyroclastic series of welded and nonwelded vitric and crystalline tuffs that range from mafic to rhyolitic in composition.

Quaternary alluvial deposits lie unconformably above all older units and consist primarily of Late Pliocene and Pleistocene alluvial fan, lacustrine, stream channel, and terrace deposits. These units may reach a combined thickness of many thousands of feet in the valley centers.

These geologic units have been grouped into ight rock and four basin-fill geologic units for use in discussing potential aggregate sources. The grouping of these units was based on similarities in physical and chemical characteristics and map scale limitations. The resulting units simplify discussion and presentation without altering the conclusions of the study.

## 3.2.1 Rock Units

Geologic rock units were grouped into the following eight categories (Drawing 2): quartzite (Qtz), limestone (Ls), dolomite (Do), carbonate rocks undifferentiated (Cau), sedimentary rocks undifferentiated (Su), granitic rocks (Gr), basalt (Vb), and volcanic rocks undifferentiated (Vu). Class II granitic rocks that crop out in the southern portion of the Bristol Range are of limited areal extent and will not be discussed.

#### 3.2.1.1 Quartzite - Qtz

Two lower Paleozoic quartzite deposits, the Prospect Mountain and Eureka quartzites, crop out in the Valley-Specific study area. Major deposits of the Prospect Mountain Quartzite are located along the east-central and southeastern margin of the site area along the west flank of the Highland Range, in the southern end of the Chief Range, and within the west-central portion of the Delamar Mountains (Drawing 2). The formation consists of reddish brown to white, thin to massively bedded, well indurated, fine-grained quartzite with interbeds of less resistant quartzite, micaceous shale, pebble conglomerates, and arkosic sandstone layers. Diabase dikes and sills of basaltic appearance locally intrude the formation.

The Eureka quartzite crops out as small units in the central portion of the study area. It is thin, generally less than 500 feet (150 m) thick, and because of its close association with the Pogonip Group (Cau) is often mapped with this

**fuero** national, me.

formation. Quartzite units are present at the north end of Burnt Springs and North Pahroc ranges and the south end of the Ely Springs Range. The formation is white or light gray in appearance, vitreous, sugary, fine- to medium-grained, massive orthoguartzite. Interbedded sandstones and dolomitic sandstones occur at the top and bottom of the formation.

#### 3.2.1.2 Limestone - Ls

Limestone is a carbonate rock which is hard, durable, medium-to massively bedded and a major cliff former within the study area. Mapped units represent upper Paleozoic sediments principally of Mississippian, Pennsylvanian, and Permian age. Formations represented include the Pogonip Group, the Joanna, Mercury, and unnamed Pennsylvanian and Permian limestones. The limestones are typically medium to dark gray, fine- to medium-grained, fossiliferous, and sparsely cherty, with well-developed bedding and jointing. This unit is mapped chiefly in the northern portion of the study area, with major deposits occurring in the Grassy and Dutch John mountains, and at the northern end of the North Pahroc Range.

## 3.2.1.3 Dolomite - Do

Dolomite is a high magnesium carbonate rock that is characteristically dark to medium gray in appearance, medium-grained, sparsely to moderately cherty, hard, with well-developed bedding and jointing. Principal formations that comprise the bulk of this unit are the lower Paleozoic Ely Springs, Laketown, Sevy, and Simonson dolomites. Major deposits are mapped in the Hiko

TUORO NATIONAL, IND.

Range west of Pahroc Valley, within the Schell Range west of Muleshoe Valley, and the Ely Springs Range.

## 3.2.1.4 Carbonate Rocks Undifferentiated - Cau

Materials classified as undifferentiated carbonate rocks include thick, complex sequences of limestone and dolomite with thin interbeds of sandstone, shale, and siltstone. Individual units are not delineated separately due to map scale limitations and the highly interbedded nature of these units. Principal formations in this unit include the Highland Peak, Guilmette, and unnamed Permian and Pennsylvanian deposits. These rocks are typically light to dark gray in appearance, thinly to massively bedded, hard, cherty, fossiliferous, and are durable cliff formers. Undifferentiated carbonate units are the most extensive of the mapped sedimentary rock units within the study The Briston and Highland Ranges along the east-central margins of the site are almost entirely mapped as undifferentiated carbonate rocks.

## 3.2.1.5 Sedimentary Rocks Undifferentiated - Su

Geologic formations mapped as undifferentiated sedimentary rocks include interbedded sandstone, shale, dolomite, limestone, and quartzite that may have been slightly metamorphosed in some areas. These deposits are characterized by poorly indurated material and complex, thin to medium bedding. The highly interbedded nature of these units prevents separation into individual rock types (limestones, dolomites). Undifferentiated sedimentary rocks are not a major unit within the site region

and are located primarily in small areas along the west and east margins in the central study area.

#### 3.2.1.6 Basalt - Vb

Tertiary basalt mapped in the study area is characteristically dense, dark gray to black, medium to thick bedded, locally vesicular, and poorly jointed. Occassionally, interbeds of volcanic agglomerate and pumice are present. Basalt is of minor extent and outcrops primarily in and adjacent to the North Pahroc Range.

### 3.2.1.7 Volcanic Rocks Undifferentiated

Undifferentiated volcanic rocks comprise the most extensive rock unit in the study area. They range from Cretaceous to Pliocene in age and consist predominantly of welded and nonwelded pyroclastics (air falls, ash flows, ignimbrites) of rhyolitic and andesitic composition.

These volcanics also include intravolcanic sedimentary rock consisting primarily of gravel, sand, and silt. Individual rock units have not been delineated because of map scale limitations and complex, but similar composition.

#### 3.2.2 Basin-Fill Units

Four basin-fill units are mapped and labelled within the study area (Drawing 2). These consist of alluvial fan (Aaf), older lacustrine (Aol), stream channel and terrace (Aal), and undifferentiated alluvial deposits (Au). Gravel (g) and sand (s) grain-size designations have been assigned basin-fill units in

fuene national, mo.

the Verification mapped areas (e.g. Aafg). Recent playa deposits, a fifth basin-fill unit, are also present in Dry Lake and Delamar valleys, but these are labelled as unsuitable aggregate sources and will not be discussed.

## 3.2.2.1 Older Lacustrine Deposits - Aol

Older lacustrine deposits were formed during late Pliocene/early Pleistocene time in response to a much wetter climate. These deposits are located at topographically higher elevations than recent playa deposits in the valley centers and are usually intermixed with or overlain by alluvial fan deposits. They range from coarse gravels to sands, silts, and clays. Classification of these deposits depends primarily on texture and clast composition. They occur principally in portions of Dry Lake Valley and on the flanks of Pahranagat Valley, west of the Pahroc Valley study area (Drawing 2).

#### 3.2.2.2 Alluvial Fan Deposits - Aaf

Alluvial fans bordering the mountain fronts and extending out into the valley basins are the most extensive basin-fill deposits within the study area. They are typically heterogeneous to poorly stratified mixtures of boulders, cobbles, gravel, sand, silt, and clay that grade from very coarse-grained near the rock/alluvium contact to fine-grained near the valley centers. Individual fan units contain poorly to well graded, angular to subangular particles and exhibit considerable lateral and vertical textural variation. Composition of the surrounding source rock strongly controls the textural properties of material found

Tuess HATISHAL, HIG.

in alluvial fan deposits. Fan units formed at the base of carbonate or quartzitic rocks are characteristically coarse grained, whereas fans developed from volcanic sources tend to be finer grained.

Caliche development in soils, a natural process of soil development in arid climates, ranges from none in younger fans to Stage III (Appendix B) in older units.

## 3.2.2.3 Stream Channel and Terrace Deposits - Aal

Stream channel and terrace deposits within the study area are associated with primary and secondary eph meral streams. Secondary ephemeral streams commonly transect alluvial fan deposits and trend normal to the ranges toward the valley axis. There, they terminate in a central playa area (Dry Lake, Delamar Lake) or a primary drainage system (Muleshoe Valley). Most are too small to be depicted on Drawing 2 and have been grouped with adjacent, more prominent units (i.e., alluvial fan, undifferentiated alluvium). These deposits vary from homogeneous to poorly stratified mixtures of sand, gravel, cobbles, and boulders near mountain fronts to sands, silts, and clays near valley centers.

### 3.2.2.4 Alluvial Deposits Undifferentiated - Au

Undifferentiated alluvial deposits consist of combinations of basin-fill units that were not delineated and mapped during the Verification program. Included in this group are alluvial fans, older lacustrine, stream channel, stream terrace, and pediment deposits. These alluvial deposits are homogeneous to stratified

**FURRO NATIONAL, ING.** 

mixtures of boulders, cobbles, gravel, sand, silt, and clay derived from a wide range of rock types. Composition varies according to the characteristics of the individual units and the source rock type. Undifferentiated alluvial deposits are generally located along the inside margins of the valley-specific boundaries around the study region (Drawing 2).

## 4.0 POTENTIAL AGGREGATE SOURCES

Based on the results of field visual observations and aggregate testing, potential basin-fill and rock sources were divided into three basic material types (i.e., coarse, fine, and crushed rock) and classified into one of the three use categories (Section 2.5). Basin-fill deposits tested in the study area may be placed within a multiple type category, (coarse and fine aggregate source). Coarse aggregate is defined as plus 0.185 inch (4.699 mm) fine gravel to boulders and fine aggregate is defined as minus 0.375 inch (9.52 mm) coarse to fine sand.

Classification boundaries (Drawing 2) of basin-fill aggregate sources were generalized and will require additional studies to accurately define their location. Boundaries of identified crushed rock sources are based on the areal map extent of the geologic formations tested (i.e., Eureka Quartzite, Guilmette Formation, Pogonip Group) and not on the aggregate geologic unit (i.e., Cau, Do, Qtz) described in Section 3.2.1.

In the following discussion, the best potential coarse, fine, or crushed rock source within each Class I and Class II category is presented first; followed by successively less probable sources. This ranking of deposits is preliminary and based upon an analysis of Fugro National and exisiting data.

TURRE HATISHAL, ING

# 4.1 BASIN-FILL SOURCES

# 4.1.1 Coarse Aggregate

# 4.1.1.1 Potentially Suitable Concrete Aggregate and Road Base Material Sources - Class I

Extensive Class I coarse aggregate sources are located along the east side of Dry Lake Valley in alluvial fan units bordering the Class I crushed rock sources in Bristol, Highland Peak, West, Ely Springs, and Burnt Springs ranges (Drawing 2). The alluvial fan units consist predominantly of moderately to moderately well graded, sandy gravels with subangular to subrounded carbonate and quartzite clasts. Laboratory test data indicate these deposits have acceptable abrasion, soundness, and alkali reactivity values for Class I coarse material (Appendix A). Sieve analysis of these samples suggest that the fan deposits are biased toward the fine end and may lack material in the coarse fraction for crushing. Overburden averages 1 to 3 meters and consists predominantly of caliche cemented gravels (Stage II to III).

Access to these deposits is provided by several unpaved roads that crisscross the area and minability is considered good to excellent. Additional field reconnaissance and testing will be necessary to accurately define the limits of this source.

Class I coarse aggregate deposits are also present in older lacustrine deposits (Aolg) within Pahranagat Valley southwest of Pahroc Valley (Drawing 2). These deposits consist of moderately well-graded, medium dense to dense, stratified sandy gravels composed primarily of carbonate clasts. Coarse fragments are

**FUGNO NATIONAL, ING.** 

subrounded and sufficient material greater than 3/4-inch exists for crushing. Testing was completed on two samples at widely separated locations and test results are available from three State of Nevada Highway pits. Results were positive, with acceptable losses in the abrasion and soundness tests. Overburden ranged from 1 to 5 meters (averaging 2.5 meters) and consists primarily of sandy material.

Limited coarse alluvial fan deposits (Aafg) in east-central Delamar Valley were also identified as Class I aggregate sources (Drawing 2). The unit consists of moderately well-graded, medium dense, sandy gravels derived primarily from nearby quartzite and carbonate rocks. Seive analysis indicates sufficient quantities of material exist above the 3/4-inch size for crushing. Abrasion and soundness losses were within acceptable limits but testing for alkali reactivity was not made on this sample. Overburden thickness averages less than 1 meter on this deposit.

Additional Class I coarse aggregate sources are present in alluvial fan deposits east of Dutch John Mountain at the north end of the study area. These deposits consist of medium dense, poorly graded sandy gravels with overburden averaging less than 1 meter in thickness. Although boundaries of this unit could not be drawn from the field reconnaissance and limited laboratory testing, field observations suggest that most alluvial fan units bordering Class I rock sources at the northern end of the study area may qualify as Class I aggregate sources.

funco national, mo.

# 4.1.1.2 Possibly Unsuitable Concrete Aggregate/Potentially Suitable Road-Base Material Sources - Class II

A limited stream channel deposit in Antelope Canyon, just north of Caliente, Nevada, was identified during the investigation as a Class II source of coarse aggregate. This deposit is composed primarily of quartzitic clasts derived from the Prospect Mountain Quartzite (Class II rock source). The deposit consists of medium dense, moderately well-graded, sandy gravel with subangular to subrounded clasts. Test results indicate an acceptable abrasion loss but lack of soundness results require a Class II ranking. A favorable soundness test would qualify this unit as Class I.

Based on field observations, Class II coarse material may be present in alluvial fans near the rock/ alluvium contact of nearly all mountain ranges. Access and mining of these sources should be good to excellent across the study region.

# 4.1.1.3 Unsuitable Concrete Aggregate or Road Base Material Sources - Class III

No unsuitable coarse aggregate sources were identified in the study area during the Valley-Specific investigation.

# 4.1.2 Fine Aggregate

# 4.1.2.1 Potentially Suitable Concrete Aggregate and Road-Base Material Sources-Class I

Class I fine aggregate sources are located in alluvial fan deposits bordering the north end of the Bristol Mountain Range and consist of medium dense, moderately well-graded, gravelly sands (Drawing 2). Gravel clasts within the unit are derived

FURRO HATIUNAL, ING.

predominantly from Class I carbonate rocks. Soundness test results are within Class I standards for fine aggregate (Table 2). Field observations indicate that deleterious substances are minor and the overburden thickness averages between 1 and 2 meters. The untested coarse aggregate content ranges from 20 to 40 percent and based on results of aggregate tests for coarse units in the same general fan complex, may also qualify as a Class I source. Access is provided by several unpaved roads that traverse the alluvial fan complex. Minability is considered good to excellent. Boundaries of Class I fine aggregate sources could not be delineated at this level of investigation and will require additional field studies and testing to define accurately.

Class I fine aggregates sources were also identified in alluvial fan deposits east of Dutch John Mountain in the northern portion of the study area. These deposits are predominantly poorly graded sandy gravels that meet Class I requirements for coarse (Section 4.1.1.1) and fine aggregate sources (multiple source). Boundaries of this unit could not be defined at this level of investigation. Based on field observations, other potential Class I fine aggregate sources may exist in alluvial fan or older lacustrine deposits derived from detritus of identified Class I crushed rock sources.

4.1.2.2 Possibly Unsuitable Concrete Aggregate/Potentially Suitable Road-Base Materials Sources - Class II

Class II fine aggregate sources are located in alluvial fan units that receive sediments from the Bristol, Highland, and

**firms** hatismal, inc.

Burnt Springs ranges (Drawing 2). These deposits consist of moderately well graded, medium dense, gravelly sands and sandy gravels predominantly of carbonate rock origin. Gravel comprises from 13 to 55 percent of the sieved samples with clasts consisting primarily of limestones and dolomites derived from the nearby mountain ranges. Soundness losses were unacceptable and alkali reactivity tests were not run on these samples.

Abrasion and soundness tests completed for the coarse material from the same alluvial fan complex are well within Class I standards (Table 2). Based on these results, aggregate sources in these areas may provide good multiple sources where gravels comprise a significant percentage of the deposit (Section 4.1.1.1).

An additional Class II fine aggregate source of limited areal extent was noted in a stream channel deposit in Antelope Canyon, just north of Caliente, Nevada. Sand-sized particles comprise up to 45 percent of this sandy gravel multiple source unit whose coarse fraction tested as a Class II coarse aggregate source.

Boundaries of Class II fine aggregate sources could not be delineated on Drawing 2 at this level of investigation and will require additional field reconnaissance and testing to accurately delineate. Additional sources of Class II fine aggregate are probably available in almost all alluvial fan units bordering Class I crushed rock sources.

**- FUORO HATIONAL, INC** 

# 4.1.2.3 Unsuitable Concrete Aggregate or Road-Base Material Sources - Class III

Class III fine aggregate sources are located in the valley basins and are comprised predominantly of older lacustrine and recent playa deposits (Drawing 2). These sediments are typically interbedded and stratified moderately dense fine sand, silt, and clay.

### 4.2 CRUSHED ROCK SOURCES

# 4.2.1 Potentially Suitable Concrete Aggregate and Road-Base Material Sources - Class I

Class I crushed rock sources are widely distributed throughout the study area. The most extensive deposits occur in the Bristol, Highland, and Burnt Springs ranges in east-central Dry Lake Valley (Drawing 2) and consist primarily of limestones and dolomites from the Highland Peak formation and unnamed Upper Cambrian limestones and dolomites (Cau). Field observations and limited laboratory testing (Appendix A) of the Highland Peak Formation indicate that splitting characteristics are favorable for crushing and abrasion and soundness losses are moderate to low (Table 2). Alkali reactivity tests have not been completed on this formation. Limestone from this rock unit has been previously quarried at the south end of the Highland Range and used in road construction. This formation also forms the principal Class I material of the Burnt Springs Range and is the major crushed rock source in the central Delamar Mountains.

Unnamed Upper Cambrian limestones and dolomites, although not as extensive as the Highland Peak Formation, are also present as

major deposits in the Highland, Burnt Springs, and Ely Spring ranges. Limited field observations suggest that the limestones within this formation are hard, have good splitting characteristics and no observable deleterious properties. Test results show no undesireable aggregate characteristics for a Class I rock unit (Table 2), however, alkali reactivity has not been tested in this source.

Access to deposits in the Bristol and Highland ranges is provided by numerous unpaved roads from Pioche, Nevada to the east and the valley basin to the west. The minability of these deposits is considered fair to very good, depending primarily on the slope of the terrain and the repose of the rock unit. Class I deposits of the Burnt Springs and Ely Springs ranges, because of their close proximity to the valley basin, would provide an excellent, highly accessibly and minable source of Class I crushed rock aggregate for the southcentral portion of the area of investigation.

Unnamed Pennsylvanian limestones (Ls) and the Guilmette Formation (Cau) form large Class I crushed rock sources at the northern end of the study area (Drawing 2). Major deposits of Pennsylvanian limestone occur primarily within the Dutch John and Grassy mountains region, northern North Pahroc Range, and as small units in the Schell Creek Range. Abrasion, soundness, and alkali reactivity test results are all well within Class I requirements. Field observations indicate that the formation is hard to very hard, fine grained, and has slabby splitting

characteristics. Existing unpaved roads provide good access to exposures of this formation located near the rock/alluvium contact and the minability of this unit is generally considered good.

The Guilmette Formation forms numerous bedrock highs and low hills in the northern half of the Dry Lake study area. Scattered small knolls composed of rocks primarily from this formation lie within the valley basin parallel to and east of the The Guilmette Formation forms about one-North Pahroc Range. half of the West Range in the east-central portion of the region and portions of the Schell Creek Range and Dutch John Mountain at the northern end of the study area. A small section of this unit is also located in the Hiko Range bordering Pahroc Valley in the southwest portion of the area of investigation. from laboratory testing indicates that the limestones display acceptable abrasion and soundness values. Alkali reactivity tests were not run on this unit. Field observations indicate rock jointing is favorable and deleterious materials were generally minor in extent. Access and minability is excellent, especially for those units located within the valley basin.

Class I andesitic volcanic rocks (Vu) were identified at the northern end of the Bristol Range (Drawing 2). While not considered a primary source of Class I crushed rock due to lateral and vertical lithologic variations, acceptable test results indicate that volcanic rocks of this composition could

make potentially suitable crushed rock sources in areas where unit boundaries can be defined.

A sandstone member within the Simonson Dolomite (Do) was the only Class I crushed rock aggregate source tested in Pahroc Valley. Although the formation forms major deposits within the Hiko Range in the southwest section of the region and small deposits within the Schell Creek Range at the northern end of the study area, Class I ranking was given only to the sandstone unit. Additional laboratory testing will be necessary to classify the acceptability of the entire formation as a Class I aggregate source. The access and minability of this crushed rock source is considered very good within the Hiko Range.

# 4.2.2 Possibly Unsuitable Concrete Aggregate/Potentially Suitable Road-Base Material Sources - Class II

No Class II crushed rock aggregate sources were specifically identified from the laboratory testing program. Extensive rock units indicated on Drawing 2 as Class II crushed rock sources were classified only by field visual observations. The predominant types of rock in this category are undifferentiated volcanics of a highly variable lithologic composition and certain Paleozoic carbonates and sedimentary rocks.

The Prospect Mountain Quartzite (Qtz) was identified as a Class II crushed rock source within the Chief Range at the southern end of Dry Lake Valley and in Delamar Valley within the central portion of the Delamar Range. Field observations indicate that

**fireno** HATIONAL, IND.

the quartzite is very hard, having slabby splitting characteristics, and no deleterious materials. A Class II ranking was given this formation because direct measurements of aggregate characteristics were not made. However, further examination and laboratory testing may give it a Class I designation.

# 4.2.3 Unsuitable Concrete Aggregate or Road Base Material Sources - Class III

Two crushed rock aggregate sources failed aggregate abrasion tests and were identified as Class III geologic units. The unsuitable sources included an exposure of Eureka Quartzite (Qtz) at the northern end of the Burnt Springs Range and rhyolitic tuffs (Vu) located at the southern end of Delamar Valley (Drawing 2).

### 5.0 CONCLUSIONS

Results of the Valley-Specific aggregate investigation indicate that potentially good to high quality (Classes I and II) basinfill and crushed rock aggregate sources are present within the Dry Lake, Muleshoe, Delamar, and Pahroc Valley Specific study area to meet construction requirements of the MX system (Drawing 2).

### 5.1 POTENTIAL BASIN-FILL AGGREGATE SOURCES

# 5.1.1 Coarse Aggregate

Major Class I coarse aggregate deposits listed in order of potential suitability, have been identified within the following areas:

- Alluvial fan deposits west of the Bristol, Highland, and Burnt Springs ranges in east-central Dry Lake Valley,
- Older lacustrine sediments west of Pahroc Valley (Pahranagat Valley), and
- 3. Alluvial fans bordering the Delamar Mountains in east-central Delamar Valley.

Field observations indicate additional sources of Class I coarse aggregate may be available in alluvial fan deposits adjacent to the rock/ alluvium contact of Class I crushed rock sources.

Potential Class II coarse aggregate sources are widespread and extensive in the study area. Although boundaries of specific deposits could not be delineated, they are typically located within alluvial fans flanking Class I and/or Class II rock sources.

TURRO HATIONAL, ING.

# 5.1.2 Fine Aggregate

While most coarse aggregate sources will supply quantities of fine aggregate either from the natural deposits or during processing, several fine aggregate sources were sampled and tested. Class I fine aggregate deposits were identified in alluvial fans bordering Class I rock sources at the north end of the Bristol Range and near Dutch John Mountain (multiple sources). Further field reconnaissance will be required to identify and delineate additional Class I fine aggregate sources, however, based on field observations, potential sources may exist in alluvial fan units derived from Class I rock sources.

Potential Class II fine aggregate sources are widespread and extensive in the study area. Specific deposit boundaries could not be delineated but typically occur basinward of most Class I and Class II coarse aggregate deposits and/or rock exposures.

#### 5.2 POTENTIAL CRUSHED ROCK AGGREGATE SOURCES

Class I crushed rock sources exist in most sections of the study area. The most suitable deposits and their corresponding locations are listed below:

- Unnamed Upper Cambrian Eastern Dry Lake Valley and Pennysylvanian carbonates Highland Peak Springs, West, and Chief Formation Guilmette ranges)
- Highland Peak Formation Eastern Delamar Valley (Central Delamar Mountains)

TURBO HATISHAL, INC

- 3. Unnamed Pennsylvanian limestones
  - Northern Muleshoe Valley (Schell Creek Range and Dutch John and Grassy mountains)
- 4. Guilmette Formation
- Northwestern Pahroc Valley (Hiko Range)

Class I crushed rock sources, exposed within the Burnt Springs, West and Ely Springs ranges, because of their close proximity to the valley basin and good to excellent minability, could provide crushed rock material for much of the central valley area. Undifferentiated volcanics and limited sedimentary units widely distributed throughout the study area comprise most of the Class II crushed rock sources delineated on Drawing 2.

#### 6.0 RECOMMENDATIONS FOR FUTURE STUDIES

Future aggregate studies should include a program to refine the lateral and vertical boundaries of Class I basin-fill, coarse aggregate sources and define their exact physical and chemical characteristics. The following procedures are recommended to achieve these objectives.

- 1. An examination of stereo aerial photographs of the Class I basin-fill and surrounding areas. Emphasis should be placed on the determination of grain-size and compositional variations within the preliminarily defined Class I source areas and the delineation of any subareas.
- 2. Field reconnaissance and selection of areas for sampling with standard backhoe equipment.
- 3. A laboratory aggregate testing program to evaluate the concrete making properties of the Class I basin-fill aggregate sources. This should include a concrete mix design test program and where needed, additional Los Angeles abrasion, soundness, and alkali reactivity tests.

This study would provide information on the relative economic aspects of the various Class I basin-fill sources necessary for developing plant designs and locations, mining methods, and concrete mix designs. It should be initiated immediately to minimize any impact on pre-construction planning considerations.

#### **BIBLIOGRAPHY**

- American Concrete Association, 1975, Durability of concrete: American Concrete Institute Publication, SP-47, 385 p.
- American Concrete Institute, 1977, Recommended practice for selecting proportions for normal and heavyweight concrete: American Concrete Institute, 20 p.
- , 1978, Cement and concrete terminology: American Concrete Institute Publications, SP. 19 (78), 50 p.
- American Public Works Assoc., 1970, Standard specifications for public works construction: Part 2 Construction Materials, Sec. 200 Rock Materials, p. 62-70.
- American Society for Testing and Materials, 1975, Significance of tests and properties of concrete and concrete-making materials: American Society for Testing and Materials, Special Technical Publication No. 169-A, 571 p.
- , 1978, Annual book of ASTM standards, Part 14: Concrete and Mineral Aggregates, 814 p.
- Bates, R. L., 1969, Geology of the industrial rocks and minerals: Dover Publications, Inc., New York, 459 p.
- Blanks, R., and Kennedy, H., 1955, The technology of cement and concrete, Vol. 1: John Wiley & Sons, Inc., 422 p.
- Borup, H. J., and Bagley, D. G., 1976, Soil survey of Meadow Valley area, Nevada-Utah, parts of Lincoln County, Nevada, and Iron County, Utah: U.S. Dept. Agriculture, Soil Conservation Service, 174 p.
- Brokaw, A., and Heidrick, T., 1960, Geologic map and section of the Girou Wash quadrange, White Pine County, Nevada: U.S. Geological Survey Map, GQ-476.
- Brokaw, A. L., and Barosh, P. J., 1968, Goologic map of the Rieptown quadrangle, White Pine County, Levada: U.S. Geol. Survey Map, GQ-750.
- Brokaw, A. L., Bauer, H. L., and Breitrick, R. A., 1973, Geologic map of the Ruth quadrangle, White Pine County, Nevada: U.S. Geol. Survey Map, GQ-1085.
- Brokaw, A. L., and Shawe, D. R., 1965, Geologic map and sections of the Ely SW quadrangle, White Pine County, Nevada: U.S. Geol. Survey Map, I-449.
- Brown, L., 1959, Petrography of cement and concrete: Portland Cement Research Dept., Bull. 111.

france Hational, INC.

- Carr, W. J., 1966, Geology and test potential of Timber Mountain Caldera area, Nevada: U.S. Geol. Survey, Tech. Letter NTS-174.
- Erlin, B., 1966, Methods used in petrographic studies of concrete: Portland Cement Association, Research Department Bull. 193, 17 p.
- Freedman, S., 1971, High strength concrete, Portland Cement Association, concrete Information Reprint, 17 p.
- Fritz, W. H., 1968, Geologic map and sections of the southern Cherry Creek and northern Egan Ranges, White Pine County, Nevada: Nevada Bureau of Mines Map, 35.
- Fugro National, Inc., 1978, Aggregate resources report, Department of Defense and Bureau of Land Mangement lands, southwestern United States: Cons. Report for SAMSO, 85 p.
- Gile, L. H., 1961, A classification of Ca horizons in soils in a desert region, Dona Ana County, New Mexico: Soil Sci. Soc. America Proc., v. 25, No. 1, p. 52-61.
- Hadley, D. W., 1961, Alkalai reactivity of carbonate rocks-expansion and dedolomitization: Research and Development Laboratories of the Portland Cement Association, Bull. 139, p. 462-474.
- rocks: Research and Development Laboratories of the Portland Cement Association, Bull. 176, 19 p.
- , 1968, Field and laboratory studies on the reactivity of sand-gravel aggregates: Research and Development Laboratories of the Portland Cement Association, Bull. 221, p. 17-33.
- Hose, R. K., Blake, M. C., Jr., and Smith, R., 1976, Geology and mineral resources of White Pine County, Nevada: Nevada Bureau of Mines and Geology, Bull. 85, 105 p.
- Howard, E. L., compiler, 1978, Geologic map of the eastern Great Basin, Nevada and Utah: Terra Scan Group LTD., 3 sheets.
- Ketner, K. B., 1976, Map showing high-purity quartzite in California, Nevada, Utah, Idaho and Montana: U.S. Geol. Survey Map, MF-821.
- Lerch, W., 1959, A cement-aggregate reaction that occurs with certain sand-gravel aggregates: Research and Development Laboratories of the Portland Cement Association, Bull. 122, p. 42-50.

fireno national, inc.

- McKee, E. D., and Weir, G. W., 1953, Terminology for stratification and cross-stratification in sedimentary rocks: Geol. Soc. America Bull., v. 64, p. 381-389.
- Murphy, J. B., Nichols, S. L., and Schilling, J. H., No date, Rockhound map of Nevada: Nevada Bureau of Mines and Geology, special publication 1.
- National Ready Mixed Concrete Association, 1961, Galection and use of aggregate for concrete: National Ready Mixed Concrete Association, Publication No. 101, p. 513 542.
- National Sand & Gravel Association, 1977, Compilation of ASTM standards relating to sand, gravel and concrete: NSGA Circular No. 113, NRMCA Pub. No. 137.
- Nevada Department of Highways, No date, Materials and research laboratory, aggregate test data: Unpublished.
- Nolan, T., et al., 1971, Geologic map of the Eureka Quadrangle, Eureka and White Pine Counties, Nevada: U.S. Geol. Survey Map, I-612.
- Office of State Inspector of Mines, 1977, Directory of Nevada mine operations active during calander year 1976: Nevada Industrial Commission, 59 p.
- Papke, G. K., 1973, Industrial mineral deposits of Nevada: Nevada Bureau of Mines and Geology, map 46.
- Pickett, G., 1956, Effect of aggregate on shrinkage of concrete and hypothesis concerning shrinkage: Portland Cement Association, Research Dept., Bull. 66, 5 p.
- Powers, T. C., and Steinour, H. H., 1955, An interpretation of published researches on the alkai-aggregate reaction: Research and Development Laboratories of the Portland Cement Association, Bull. 55, Part I and II, p. 497, 785.
- Reid, J. A.. 1904, Preliminary report on the building stones of Nevada, including a brief chapter on road metal: Univ. of Nevada Dept. of Geology and Mining, v. 1, no. 1, 57 p.
- Roper, H., 1960, Volume changes of concrete affected by aggregate type: Portland Cement Association, Research Dept. Bull. 123, 4 p.
- Synder, C. T., Hardman, George, and Zdenek, F. F., 1964, Pleistocene lakes in the Great Basin: U.S. Geol. Survey Map, I-416.

- **fuero** HATIGNAL, ING.

- Steinour, H. H., 1960, Concrete mix water--how impure can it be? Research and Development Laboratories of the Portland Cement Association, Bull. 119, p. 33-50.
- Steven, T. A., 1978, Geologic map of the Sevier SW quadrangle, west-central Utah: U.S. Geol. Survey Map MF 962.
- Stewart, H., and Carlson, J. E., 1978, Geologic Map of Nevada: U.S. Geol. Survey, scale 1:500,000.
- Teichert, J. A., 1959, Geology of the southern Stansbury Range: Utah Geol. and Mineral. Survey, Bull. 65, 75 p.
- Travis, R. B., 1955, Classification of rocks: Quarterly of the Colorado School of Mines, v. 50, No. 1, 98 p.
- U. S. Army Corps of Engineers, 1953, Test data, concrete aggregate in continental U.S.: U. S. Army Corps of Engineers V.1, areas 2 and 3.
- U. S. Bureau of Land Management, 1974, Nevada BLM Statistics (1974): U. S. Dept. of Interior, 20 p.
- U. S. Department of Agriculture, 1959, Soil survey, east Millard area, Utah: U. S. Dept. of Agriculture, 101 p.
- J. S. Dept. of Agriculture, 75 p.
- U. S. Department of the Interior, 1975, Concrete Manual: Water Resources Technical Publication, 627 p.
- U. S. Department of the Interior, Bureau of Mines, 1974, The Mineral Industry of Nevada.
- U. S. Department of the Interior, Bureau of Reclamation, 1966, Concrete Manual: A Manual for the Control of Concrete Construction, 642 p.
- , Lower Colorado Regional Office, Nevada Aggregate Data, Unpublished.
- rior, Bureau of Reclamation, 810 p.
- , 1975, Concrete Manual: U. S. Department of the Interior, Bureau of Reclamation, 627 p.
- U. S. Geological Survey, 1964, Mineral and water resources of Nevada: U. S. Government Printing Office, Washington, 314 p.

fuene national, inc

- Voskuil, W. H., 1966, Selected readings in mineral economics: Nevada Bureau of Mines, Report 12, 18 p.
- Waddell, J., 1976, Concrete inspection manual: International Conference of Building Officials, 332 p.
- Womack, J. C., et al., 1963, Materials manual: California Highway Transporation Agency, vol. I and II.

# APPENDIX A

Fugro National Field Station and Supplementary Test Data and Existing Test Data Summary Tables -Dry Lake, Muleshoe, Delamar, and Pahroc Valleys

\_\_\_

•

•

1

# EXPLANATION OF FUGRO NATIONAL FIELD STATION AND SUPPLEMENTARY TEST DATA

Fugro National field stations were established at locations throughout the Valley-Specific study area where detailed descriptions of potential basin-fill or rock aggregate sources were recorded (Drawing 1). All field observations and laboratory test data on samples collected at selected stations are presented in Table A-1. Data entries record conditions at specific field station locations that have been generalized in the text and Drawing 2. Detailed explanations for the column headings in Table A-1 are as follows:

# Column Heading

#### Explanation

Map Number

This sequentially arranged numbering system was established to facilitate the labelling of Fugro National field station locations and existing data sites on Drawing 1 and to list the correlating information on Tables A-1 and A-2 in an orderly arrangement.

Field Station

Fugro National field station data are comprised of information collected during:

- o The Valley-Specific Aggregate Resources Study; sequentially numbered field stations were completed by two investigative teams (A and B). The Dry Lake Candidate Deployment Area (DLCDP) designation is obsolete. The presently understood study area consists of Dry Lake, Muleshoe, Delamar, and Pahroc valleys.
- o The general aggregate investigation in Nevada (NV); R and H indicate ground and aerial reconnaissance stops, respectively.
- o The Verification study in Dry Lake (DL), Muleshoe (MS), Delamar (DM), and Pahroc

FURRE HATIENAL, ING.

# Column Heading

# Explanation

Field Station (cont.)

(P) valleys; trench data (T) were restricted to information below the soil horizon (1 to 2 meters).

Location

Lists major physiographic or cultural feature in/or near which field stations or existing data sites are situated.

Geologic Unit

Generalized basin-fill or rock geologic units at field station or existing data locations. Thirteen classifications, emphasizing age and lithologic distinctions were developed from existing geologic maps to accomodate map scale of Drawing 2.

Material Description

Except in cases where soil or rock samples were classified on laboratory results, the descriptions are based on field visual observations utilizing the Unified Soil Classification System (See Appendix C for detailed USCS information).

#### Field Observations

Boulders and/or Cobbles, Percent The estimated percentage of boulders and cobbles is based on an appraisal of the entire deposit. Cobbles have an average diameter between 3 and 12 inches (8 and 30 cm); boulders have an average diameter of 12 inches (30 cm) or more.

Gravel

Particles that will pass a 3-inch (76 mm) and are retained on No. 4 (4.75 mm) sieve.

Sand

Particles passing No. 4 sieve and retained on No. 200 (0.075 mm) sieve.

Fines

Silt or clay, soil particles passing No. 200.

Plasticity (Index)

Plasticity index is the range of water content, expressed as percentage of the weight of the oven-dried soil, through which the soil is plastic. It is defined as the liquid limit minus the plastic limit. Field classification followed standard descriptions and their ranges are as follows:

None - Nonplastic (NP) (PI, 0 - 4)

Low - Slightly plastic (PI, 4 - 15)

Medium - Medium plastic (PI, 15 - 30)

High - Highly plastic (PI, > 31)

**fuoro** national, inc.

### Column Heading

# Explanation

Hardness

A field test to identify materials that are soft or poorly bonded by estimating their resistance to impact with a rock hammer; classified as either soft, moderately hard, hard, or very hard.

Weathering

Changes in color, texture, strength, chemical composition or other properties of rock outcrops or rock particles due to the action of weather; field classified as either fresh or slight(ly) moderate(ly) or very weathered.

Deleterious Materials Substances potentially detrimental to concrete performance that may be present in aggregate; includes organic impurities, low density material, (ash, vesicules, pumice, cinders), amorphous silica (opal, chert, chalcedony), volcanic glass, caliche coatings, clay coatings, mica, gypsum, pyrite, chlorite, and friable materials, also, aggregate that may react chemically or be affected chemically by other external influences.

## Laboratory Test Data

Sieve Analysis (ASTM C 136) The determination of the proportions of particles lying within certain size ranges in granular material by separation on sieves of different size openings; 3-inch, 1 1/2-inch, 3/4-inch, 3/8-inch, No. 4, No. 8, No. 16, No. 30, No. 50, No. 100 and No. 200.

No. 8, No. 50 Asterisked entries used No. 10 and No. 40 sieves, respectively.

Abrasion Test (ASTM C 131)

A method for testing abrasion resistance of an aggregate by placing a specified amount in a steel drum ( the Los Angeles testing machine), rotating it 500 times, and determing the material worn away.

Soundness Test (ASTM C 88) CA, FA

CA = Coarse Aggregate FA = Fine Agregate

The testing of aggregates to determine their resistance to disintegration by saturated solutions of magnesium sulfate. It furnishes information helpful in judging the soundness of aggregates subject to weathering action, particularly when adequate

- fueno national, inc.

# Column Heading

# Explanation

information is not available from service records of the material exposed to actual weathering conditions.

Specific Gravity and Absorption (ASTM C 127 and 128) Methods to determine the Bulk Specific Gravity, Bulk SSD Specific Gravity (Saturated - Surface Dry Basis), and Apparent Specific Gravity and Absorption as defined in ASTM E12-70 and ASTM C 125, respectively.

Alkali Reactivity (ASTM C 289) This method covers chemical determination of the potential reactivity of an aggregate with alkalies in portland cement concrete as indicated by the amount of reaction during 24 h at 80 C between 1 N sodium hydroxide solution and aggregate that has been crushed and sieved to pass a No. 50 (300- $\mu$ m) sieve and be retained on a No. 100 (150- $\mu$ m) sieve.

Aggregate Use

- I = Class I; potentially suitable concrete aggregate and road-base material source.
- II = Class II; possibly unsuitable concrete
   aggregate/potentially suitable road base material source.
- III = Class III; unsuitable concrete aggregate or road base material source.
  - c = coarse aggregate
  - f = fine aggregate
- f/c = fine and coarse aggregate
- cr = crushed rock

All sources not specifically identified as Class I, II, or III from the abrasion, soundness, or alkali reactivity tests or the content of clay- and silt-sized particles, are designated as Class II sources.

**FURNE NATIONAL, INC.** 

			OF OLO OLO MATERIA			· ·	1210
NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	RS ? COBBLES, IT	<b>W</b> TI
MAP						BOULDERS AND/OR COB PERCENT	GRAVEL
1	DLCDP-A1	Dry Lake Valley	Qtz	Quartzite			
2	DLCDP-A2	Dry Lake Valley	Ls	Limestone			
3	DLCDP-A3	Dry Lake Valley	Aals	Gravelly Sand	SP	Т	35
4	DLCDP-A4	Dry Lake Valley	Su	Sandstone			
5	DLCDP-A5	Dry Lake Valley	Do	Dolomite			
6	DLCDP-A6	Schell Creek Mountains	Do	Dolomite			7 A
7	DLCDP-A7	Silver King Mountains	Aafs	Sandy Gravel	GP	T	1
8	DLCDP-A8	Dry Lake Valley	Vu	Welded Tuff			
9	DLCDP-A9	Burnt Peak Mountains	Su	Sandstone			
10	DLCDP-A10	Dry Lake Valley	Qtz	Quartzite			
11	DLCDP-A11	Dry Lake Valley	Do	Dolomite			
12	DLCDP-A12	Dry Lake Valley	Aals	Gravelly Sand	SP	T	
13	DLCDP-A13	Dry Lake Valley	Vu	Tuff			

				FIEL	D OBSERV	ATIONS						<del></del> -			
AND ON COSSIES.	DISTRIBUTION OF MATERIAL FINER THAN COBBLES. PERCENT  SSU  NATERIALS  DELETERIOUS  MATERIALS						S	IEVE A	NALYSI	S, PER	CENT P	ASSING	(A		
AND/DA	GRAVEL	SAND	FINES	PLAST	HARD	WEATH	MATERIALS	3"	1ጷ"	<b>¾</b> "	3/8"	NO.	NO.	NO. 16	200
					Hard	Slight	None								
					Hard	Slight	<5% Chert								
T	35	60	5	None			5% Caliche Nodules			:					
					Very Hard	Slight	Friable					!			
					Hard	Slight	<5% Chert, Calcite Veins					l			
					Hard	Slight	Calcite Veins								
Ť	50	45	5	None			<5% Caliche Nodules		ļ						
	. 1				Hard	Moderate	Pumice		I				  - 		
					Very Hard	Fresh	None								
					Hard	Slight	None				,		:		
					Hard	Slight	Calcite Veins				i				
T	15	80	5	None			15% Volcanic Ash								
					Soft	Slight	Ash								
								L	L	·			<del>*</del>		

	LABORATORY TEST DATA															
25111	ACTM	C 136	`		SION ST C 131)	CUINDME	SS TEST				C 127	AND C	128)			ALM
- 33 IN	mICA) E	0 130	,		ABRASION TEST ASTM C 131	(ASTM	C 88)		ARSE A	GGREGA RAVITY	TE   = =		INE AG IFIC GR	GREGAT AVITY	<u> </u>	REACT (ASTM
NO. 16	NO.	NO. 50	NO. 100	NO. 200	PERCENT WEAR	PERCEN	T LOSS	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	BULK	BULK	APPAR- ENT	PERCENT IBSORPTION	CA
		<u></u>				•	- 1 %						, <u></u>			
								<u>}</u>	]							
7				[ 												
					22.3	1.11		2.80	2.82	2.85	0.57					Innocuous
	}															

	ALM REACT (ASTM	(AL1 TVITY C 289)	GGREGATE USE
PERCENT IBSORPTI	CA	FA	AGI
			Her
			IIcr
			IIf/c
			IIcr
	Innocuous		Icr
			IIcr
			IIc/f
			IIcr
			IIf
			IIcr
		ļ	

FUGRO NATIONAL FIELD STATION AND SUPPLEMENTARY TEST DATA DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE - DMO

TABLE A-1 PAGE 1 OF 9

MAP NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	BOULDERS AND/OR COBBLES, PERCENT	ERLYF! _ EE
14	DLCDP-A14	Dry Lake Valley	Aafs	Gravelly Sand	SP-SM		
15	DLCDP-A15	Dry Lake Valley	Aafs	Gravelly Sand	SP-SM GP-GM	!	
16	DLCDP-A16	Dry Lake Valley	Vu	Andesite			
17	DLCDP-A17	Dry Lake Valley	Aafg	Silty Sandy Gravel	GM		
18	DLCDP-A18	Dry Lake Valley	Aafs	Gravelly Sand	SM		
19	DLCDP-A19	Dry Lake Valley	Aals	Gravelly Sand	SP-SM		
20	DLCDP-A20	Dry Lake Valley	Aafs	Silty Sand	SM	0	10
21	DLCDP-A21	Burnt Spring Range	Aafs	Sandy Gravel	GP-GM		
22	DLCDP-A22	Dry Lake Valley	Vu	Ash Flow			
23	DLCDP-A23	Burnt Spring Range	Ls	Limestone			
24	DLCDP-A24	Burnt Spring Range	Ls	Limestone			
25	DLCDP-A25	Dry Lake Valley	Aals	Sandy Gravel	GP		

		<del></del>	FIEL	D OBSERV	ATIONS			<del></del>			<del></del>			
MATE THA	RIBUTII RIAL F N COBB PERCENT	INER LES,	PLASTICITY	HARDMESS	FEATHERING	DELETERIOUS		S	IEVE A	NALYSI	S. PER	CENT P	ASSING	(ASTM
GRAVEL	SAND	FINES	PLAS	HAR	WEATI	MATERIALS	3"	15,"	<b>¾</b> "	36"	NO.	NO.	NQ. 16	NO. 30
			None			10% Caliche Nodules and Friable Mtls.				100	78.8	62.7	46.7	36.2
			None			12% Caliche Nodules	98	94.7	87.4	72.1	55.3	44.2	33.8	25.2
	!	:		Hard	Slight	Volcanic Glass and Vesicles								
			None			20% Caliche and Clay Nodules	100	98.3	91.8	76.2	54.5	43.1	36.1	31.1
			None			15% Caliche Nodules				100	81.1	70.2	60.4	51.9
			None			5% Caliche Nodules 5% Pumice	!			100	86.9	64.8	43.4	28.5
10	70	20	None		:	None		<u> </u>				 		
			None	i I		Volcanic Glass, Caliche Coatings	93.7	84.3	73.3	59.7	46.5	38.4	30.2	22.9
				Mod. Hard	Moderate	Volcanic Glass and Pumice								
				Hard	Slight	None		<u> </u>						
	j			Hard	Slight	Calcite Veins				]				
	ļ					10% Intermediate Volcanics	100	99	90.2	67.6	66.5			

ľ	LABORATORY TEST DATA  SPECIFIC GRAVITY AND ABSORPTION																
	(ASTM	C 136	)		ABRASION TEST ASTH C 131)	SOUNDNE	SS TEST C 88)	HI		CIFIC ( (ASTM GGREGA	C 127	AND A	128)	I ON GREGAT		ALK REACT	IVIT
					AST AST	(20.	C 00)	SPECI	FIC GR	TAVITY	==	SPECI	FIC GR	YTIVA	1. 1.00	(ASTM	U 200
	NO. 30	NO. 50	NO. 100	NO. 200	PERCENT WEAR	PERCEN CA	T LOSS	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	CA	
line	36.2	27.1	15.9	9.7			12.6					2.63	2.68	2.77	1.96		
	<b>25.</b> 2	17.0	11.4	7.5	25.3	8.80	18.64	2.59	2.65	2.73	1.98						
					23.2	7.87		2.56	2.61	2.69	1.92			<u> </u>		Potentially Deleterious	
	31.1	26.6	22.2	17.7	29.8	13.58	18.08	2.58	2.65	2.72	2.05		<b>!</b>			Innocuous	Ing
	51.9	42.2	33.2	25.9		ļ	21.85						   				
	28.5	18.7	13.9	11.3			30.13							2.69	3.9		
2	22.9	14.9	9.5	6.5	25.0	13.79	30.23										
					26.5	2.88											
	;				27.9	11.19		2.56	2.61	2.70	1.99					Innocuous	

DRY LARE.

TION GREGAT RAVITY		ALK REACT (ASTM	ALI IVITY C 289)	AGGREGATE USE
APPAR- ENT	PERCENT PROBLION	CA	FA	P
2.77	1.96	-		IIf
		Potentially Deleterious	Tanasiais	Ic IIf Icr
		Innocuous	Innocuous	Ic IIf
				IIf
2.69	3.9			IIf
	: :			IIf
				Ic IIf
				IIcr
				Icr
				IIcr
		Innocuous		Ic

FUGRO NATIONAL FIELD STATION
AND SUPPLEMENTARY TEST DATA
DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - BMO

TABLE A-1 PAGE 2 OF G

JORO MATIONAL ING.

P NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	RS COBBLES, T	PAST MATE
MAP						BOULDERS AND/OR CO PERCENT	CRAVEL
26	DLCDP-A26	Dry Lake Valley	Vu	Welded Tuff			
27	DLCDP-A27	Dry Lake Valley	Vu	Rhyolite			
28	DLCDP-A28	Dry Lake Valley	Aafs	Gravelly Sand	SP	Т	35
29	DLCDP-A29	Highland Range	Ls	Limestone		]	
30	DLCDP-A30	Dry Lake Valley	Aol	Sandy Gravel	GP		
31	DLCDP-A31	Dry Lake Valley	Aaf	Gravelly Sand	SP	10	45
32	DLCDP-A32	  Pahranagat   Valley	Aol	Gravelly Sand	SP		
33	DLCDP-A33	Pahranagat Valley	Aol	Sandy Gravel	GP		
34	DLCDP-A34	Pahroc Valley	Vu	Rhyolite	!		
35	DLCDP-A35	Pahroc Valley	Su	Sandstone			
36	DLCDP-A36	Pahroc Valley	Ls	Limestone			
37	DLCDP-A37	Pahroc Valley	Aafs	Sandy Gravel	GP	5	7

				FIEL	D OBSERV				· · · · · · · · · · · · · · · · · · ·				***************************************		
AND/OR COBBLES. PERCENT	DISTE MATE THA	RIBUTIO RIAL F N COBB PERCENT	INER Les,	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS		S	IEVE AI	NALYSI	S, PER	CENT P	ASSING	
AND/OR Percent	GRAVEL	SAND	FINES	PLAST	HARD	WEATH	MATERIALS	3	14"	<b>¾"</b>	3/8 "	NO. 4	NO. 8	NO. 16	
					Hard	Slight	Volcanic Glass and Pumice								
					Mod. Hard	Slight	Volcanic Glass and Pumice								
T	35	60	5	None			Volcanic Glass, Ash, Caliche Nodules			;					
					Hard	Slight	None								
				None			<5% Chert, Caliche Coatings	90.3	72.6	51.7	35.9	25.7			
10	45	55	T	None			5% Chert, Caliche, Volcanic Glass								
				None			Caliche Coatings and Low Density Mtls.	100	97.8	90.0	78.7	59.8	44.7	30.9	2
				None			10% Incermediate Volcanics, Chert, Caliche	80.5	58.4	38.4	25.0	16.5			
					Mod. Hard	Moderate	Volcanic Glass, Pumice, Mica		'						
					Hard	Slight	None						i :		
					Hard	Slight	<5% Chert		:						
5	70	30	0	None			<5% Chert								
			<u> </u>	<u> </u>				<u> </u>	<u> </u>		L	<u> </u>	L		Ц

LABORATORY TEST DATA

L	SPECIFIC GRAVITY AND ABSORPTION																
	PASSING	MT2A\	art n	<b>)</b>		ABRASION TEST ISTM C 131)	CUINDNE	SS TEST			(ASTM	C 127	AND C	128)			Of
ľ	NOOTING	i (noim	0 100	,		ABRA TE	(ASTM	C 88)		ARSE A FIC GR	GGREGA			INE AG	GREGAT		RE (AS
1	MO	NO	MO	NO.	NO.	PERCENT	PERCEN	T LOSS		r	APPAR-	PERCENT IBSORPTION		BULK	APPAR-	PERCENT 1850RPT 101	
Ľ.	NO. 16	NO. 30	NO. 50	100	200	WEAR	CA	FA	BULK	SSD	ENT	OSBY	BULK	SSD	ENT	PEI	CA .
	30.9	20.9	12.4	7.5	4.6	27.3 24.3 34.7 23.9	1.91 4.14 18.15 3.86	35.30	2.68 2.45 2.54	2.58	2.74 2.66 2.66	0.71 3.31 1.81					Potentia Deleteri

) )

	GREGAT AVITY APPAR	PERCENT BSORPTION	REACT (ASTM	ALI IVITY C 289)	AGGREGATE USE
	ENT	ABSO!	CA	FA	
					IIcr
					IIcr
					IIf/c
					Icr
					Ic IIf
					IIf/c
			Potentially Deleterious	Deleterious	IIf/c
					Ic
					IIcr
				Icr	
				IIcr	
					IIc/f
1					{

FUGRO NATIONAL FIELD STATION AND SUPPLEMENTARY TEST DATA DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE - BMD TABLE A-1 PAGE 3 OF 9

4

	Y	T	T				
MAP NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	BOULDERS AND/OR COBBLES PERCENT	GRAVEL
38	DLCDP-A38	Dry Lake Valley	Do	Dolomite			
39	DLCDP-A39	Dry Lake Valley	Vu Vu	Andesite			
40	DLCDP-A40	Dry Lake Valley	Qtz	Quartzite			
41	DLCDP-A41	Dry Lake Valley	Aol	Gravelly Sand	SP	T	25
42	DLCDP-A42	Dry Lake Valley	Aafs	Gravelly Sand	SP	0	30
43	DLCDP-A43	Dry Lake Valley	Aafg	Sandy Gravel	GP		
44	DLCDP-A44	Dry Lake Valley	Aafs	Silty Sandy Gravel	GM		<u> </u>
45	DLCDP-A45	Antelope Canyon	Aal	Gravelly Sand	SP	T	45
46	DLCDP-A46	Antelope Canyon	Qtz	Quartzite			
47	DLCDP-A47	Muleshoe Valley	Ls	Limestone			
48	DLCDP-A48	Antelope Canyon	Aal	Sandy Gravel	GP		
49	DLCDP-A49	Dutch John Mountains	Aaf	Silty Gravel	GM		
50	DLCDP-A50	Bristol Pass	Aaf	Gravelly Sand	SP	T	40

				FIEL	D OBSERVA	TIONS									
A	MATE	RIBUTIO RIAL F N COBB! PERCENT	INER LES,	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS Materials		S	IEVE AI	NALYSI	S, PER	CENT PI	ISSING	(ASTI
ALS MANUAL	GRAVEL	SAND	FINES	PLAS	HAR	WEAT	MATERIALS	3"	1岁"	<b>*</b> "	36"	NO.	NO.	NO. 16	NO.
				:	Hard	Slight	Calcite Veins								:
					Hard	Slight	Volcanic Glass, Pumice, Vesicles				Ti.			1	
					Very Hard	Fresh	None								
	25	75	0	None			Chert, Volcanic Glass, Caliche Coatings						•		
	30	70	T	None			Volcanic Glass, Caliche Coatings		:			İ			:
				None			Volcanic Glass, Caliche Coatings	79.6	59.3	46.2	39.0	34.4			
				None			15% Ash Fragments and Clay Lumps	94.7	93.2	81.7	63.9	45.8	36.1	29.1	24.8
	45	55	Т	None			Low Density Material	li							
					Very Hard	Slight	None								
					Hard	Slight	Calcite Veins								
				None			Caliche Coatings, Volcanic Ash	97.8	83.7	70.0	60.8	52.5	45.4	35.1	23.
				None			10% Chert, Caliche Coatings	j.	100	96.4	73.7	38.2	28.2	23.5	21.
	40	60	T	None			Chert, Pumice								

						TEST DA	TA										
(ASTM	C 136	)		ABRASION TEST (ASTH C 131)	S OUNDNI (ASTM	ESS TEST		ARSE .	CIFIC ( (ASTM (GGREGA RAVITY	C 127	AMD C	128)	REGATE	100	REACT	LKALI CTIVITY M C 289)	
NO. 30	NO. 50	NO. 100	NO. 200	PERCENT WEAR	PERCEN	T LOSS	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	BULK	BULK	APPAR- ENT	PERCENT IBSORPTION	CA	FA	
24.8	21.6	18.8	15.8	64.9 20.4 27.8	11.97	18.16	2.54	2.59	2.67	1.96							
23.1	12.0	6.9	4.7	22.7		20.33											
21.1	20.3	19.6	17.6	25.6	5.10	8.00	2.63	2.67	2.75	1.56	2.56	2.61	2.68	1.79			
				27.5	5.30		2.60	2.65	2.73	1.84							

FUG ANG DRY LAKE, W

MX SI

VO

EGAT VITY		ALN REACT (ASTN	ALI IVITY C 289)	AGGREGATE USE
PPAR- ENT	PERCENT ABSORPTION	CA	FA	¥
				IIcr
				IIcr
				IIcr
				IIf
				IIf/c
				Ic
				Ic II?
				I)f/c
				IIcr
				Iler
				IIc/f
2.68	1.79			Ic/f
				Ic IIf

FUGRO NATIONAL FIELD STATION
AND SUPPLEMENTARY TEST DATA
DRY LAKE, MULESHOE, DELAWAR, AND PANROC VALLEYS

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE - BMG

TABLE A-1 Pabe 4 of B

USRO NATIONAL INC

P NUMBER	FIELD STATION	LOCATION	GEOLOGIC UNIT	MATERIAL Description	USCS Symbol	LDERS FOR COSSIES, SENT	
MAP						BOULDE AND/OR PERCEN	
51	DLCDP-A51	Delamar Valley	Ls	Limestone			
52	DLCDP-A52	Delamar Valley	Vu	Ignimbrite			
53	DLCDP-A53	Delamar Valley	Vu	Rhyolite			
54	DLCDP-A54	Delamar Valley	Vu	Andesite			
55	DLCDP-A55	Delamar Valley	Vu	Rhyolitic Tuff			
56	DLCDP-B1	Muleshoe Valley	Ls	Limestone			
57	DLCDP-B2	Sidehill Valley	Ls	Limestone			
58	DLCDP-B3	Steward Spring	Ls	Limestone			
59	DLCDP-B4	Muleshoe Valley	Ls	Limestone			
60	DLCDP-B5	Muleshoe Valley	Vu	Andesite			
61	DLCDP-B6	Muleshoe Valley	Vu	Welded Tuff			
62	DLCDP-B7	Miller Summit	Vu	Welded Ash Flow			

FIELD OBSERVATIONS					<del></del>										
				FIEL	O OBSERV	ATIONS						-			
	MATE Tha	RIBUTION COBB PERCEN	INER LES,	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS		s	IEVE A	NALYSIS	S, PER	CENT P	ASS 'NG	(AST
PERCENT	GRAVEL	SAND	FINES	PLAS	HARI	WEAT	MATERIALS	3"	ነአ"	<b>*</b> "	₩"	NO.	NO.	NO. 16	NO. 30
					Hard	Slight	<5% Chert								
					Hard	Slight	Volcanic Glass. Low Density Materials								! !
					Hard	Slight	Volcanic Glass, Low Density Materials								
	į				Hard	Slight	Volcanic Glass								1
					Mod. Hard	Moderate	Volcanic Glass, Pumice, Vesicles								
					Hard	Slight	None								
					Very Hard	Fresh	None								
					Very Hard	Fresh	Chert		'						
					Hard	Slight	Chert					:	·		
					Very Hard	Slight	-Volcanic Glass	·			:				
					Hard	Slight	Volcanic Glass, Pumice					İ			
					Hard	Slight	Volcanic Glass			ł					
														<u> </u>	

<b>9</b> .	NO. 30	NO. 50	NO. 100	NO. 200	PERCENT WEAR	PERCEN CA	T LOSS	BULK	BULK	APPAR- ENT	PERCE ABSORP	BULK	BULK	APPAR- ENT	PERCE	CA
													İ			
										ļ						
						l								}	İ	}
			!		62.5											Potentially Deleterious
					35.2	5.61		2.67	2.68	2.70	0.47		!			
	1	i ·	j :													
	] ]															
							}									
						İ										
						}			ı							
				}					ĺ							
L																

ORY LA

DEPART

7100	ALI REACI (ASTM	KALI TIVITY C 289)	AGGREGATE USE
ABSORPTION	CA	FA	
			IIcr
ļ			IIcr
			IIcr
			IIcr
	Potentially Deleterious		IIcr
			Icr
			IIcr
			IIcr
1			IIcr

FUGRO NATIONAL FIELD STATION AND SUPPLEMENTARY TEST DATA DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE - SMO

TABLE A-1 PAGE 5 OF G

MAP NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	BOULDERS AMD/OR COSDLES, PERCENT	The second secon
63	DLCDP-B8	Miller Summit	Ls	Limestone			
64	NV-R-27	Chief Range	Au	Silty Sand	SP-SM		
65	NV-R-28	Chief Range	Au	Gravelly Sand	SP		
66	NV-R-30	Pioche Hills	Aaf	Sandy Gravel	GP-GC		
67	NV-R-31	Lake Valley	Aaf	Clayey Sanduff	SC-SM		
68	NV-R-32	Lake Valley	Vu	Rhyolite			
69	NV-R-33	Grassy Mountain	Aaf	Sandy Gravel	GP		
70	NV-R-85	Hiko Range	Cau	Limestone			
71	NV-R-86	Pahranagat Valley	Au	Silty Sand	SM		
72	NV-R-87	Pahranagat Valley	Aal	Silty Sand	SM		
73	NV-R-88	Pahranagat Valley	Au	Silty Sandf	SP/SW		
74	NV-R-89	Pahranagat Valley	Aaf	Silty Sand	SP-SM		
75	NV-R-90	Pahranagat Valley	Vu	Silicic Tuff			

FIELD OBSERVATIONS  DISTRIBUTION OF MATERIAL FINER > 4															-
AND/UN COBBLES, Percent	MATE Tha		INER LES,	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS		S	IEVE A	NALYSI	S, PER	CENT P	ASSING	(A
MO/OR Percen	GRAVEL	ONVS	FINES	PLAS	HAR	WEAT	MATERIALS	3"	1½"	<b>¾</b> "	34"	NO.	NO.	NO. 16	7.3
					Very Hard	Slight	Chert								And the second s
	5	80	15	Low			95% Glassy Volcanics								
	35	50	15	None			40% Glassy Volcanics							-	
	60	35	5	Low			Chert, Caliche, Clay								
	5	60	35	Low	·		80% Glassy Volcanics								
							Glassy								
		,					Chert, Caliche	100	92.7	80.5	62.3	49.2	42.0	37.3	30
					į		Chert								
	20	65	15	None			5% Glassy Volcanics, Caliche Coatings		<u> </u>						
- - -	25	60	15	None			95% Glassy Volcanics		<u> </u>						
	5	90	5	None			85% Glassy Volcanics								
	10	80	10	Mod.			100% Glassy Volcanics		ļ ļ			<u> </u> 			
							Glassy								
								1	L					<u> </u>	Ц

ı	AROR	ATORY	TEST	DATA
-	REGIN	~	1 L J I	UNIA.

L																	
		MT2A)	C 136	` <u> </u>		ABRASION TEST ASTM C 131)	CUINDAG	ESS TEST				C 127	AND C	128)			ALK REACT
	.001110	(NO1m	0 100	,		FE TE	(ASTM	C 68)			GGREGA				GREGATE	<del></del>	(ASTM
h		T	T	1	T	<del></del>	BERRE	(T. 1.666	SPEC	FIC GF		PTI	SPECI	FIC GR		E L	,
	NO. 16	NO. 30	NO. 50	NO. 100	NO. 200	PERCENT	CA	T LOSS	BULK	BULK	APPAR- ENT	PERCENT Absorption	BULK	BULK	APPAR-	PERCENT IBSORPTION	CA
	37.3	30.5			6.8	26.0	5.3										

DRY

DEF

3

GAT		ALM REACT (ASTM	ALI IVITY C 289)	AGGREGATE USE
PAR- NT	PERCENT Absorption	CA	FA	V
				IIcr
				IIf
				IIf/c
				IIc/f
	:			IIf
				IIcr
				Ic IIf
			·	IIcr
				IIf
				IIf
		!		IIf
				IIf
				IIcr
	l			

FUGRO NATIONAL FIELD STATION AND SUPPLEMENTARY TEST DAYA DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE - BMD

TABLE A-1 Page 6 of 9

VERO NATIONAL INC.

MAP NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	BOULDERS AND OR COBALES. FACENT WHAVEL HE STATES
76	NV-H-9	Chief Mountains	Qtz	Quartzite		
77	NV-H-10	Bristol Range	Cau	Limestone		
78	NV-H-1 1	Bristol Range	Cau	Limestone		
79	NV-H-15	Bristol Range	Cau	Limestone		
80	NV-H-16	Grassy Mountain	Cau	Limestone		
81	NV-H-17	Dutch John Mountain	Cau	Limestone		
82	NV-LN-1	Pahranagat Valley	Au	Gravelly Sand	SP	
83	NV-LN-3	Delamar Mountains	Su	Sandy Gravel	GP	
84	DL-T-1	Coyote Wash	Aals	Silty Sand	SP-SM	
85	DL-T-2	Dry Lake Valley	Aals	Silty Sand	SP-SM	
86	DL-T-3	Dry Lake Valley	Aafs	Gravelly Sand	SP	
87	DL-T-4	Dry Lake Valley	Aafs	Silty Sand	SP-SM	
88	DL-T-5	Dry Lake Valley	Aafs	Gravelly Sand	SP	

Transfer to the State of the St

FIELD OBSERVATIONS						<del></del>									
				FIEL	_D OBSERV/	ATIONS									
	MATER THAN	RIBUTIO RIAL FI N COBBL PERCENT	INER ILES, T	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS		\$	IEVE AI	NALYSI!	S. PER	CENT PA	ASSING	(AST
PERCENT	GRAVEL	SAND	FINES	PLAS	HAR	WEAT	MATERIALS	3"	1½"	<b>¾"</b>	34"	NO.	NO.	NO. 16	MQ. 36
							None								
		1				'	Dolomitic								
		 					Dolomitic								
							Chert								
							1 to 2% Chert	'							
							1 to 2% Chert	'							
								100	96.9	91.2	80.2	62	45.8	30.4	
								100	99.1	89.2	63.1	45.5	35.4	32.2	
								'	100	96.3	88	79.3	68.7 <sup>4</sup>		33 <sup>•</sup>
		1						'		94.2	82.8	70.6	60.8 <sup>m</sup>		43.4
								1	100	95	82	76	70 <b>*</b>		44 <b>e</b>
· ·									100	94.5	90.3	82	72 <b>*</b>		45.3
									100	90	79	61	40*		20
11			ı'	1J	<u> </u>	<u>'</u>		<u></u> '	<u>'</u>	<u></u> '	<b></b> '	<b></b> '	'ـــــــــــــــــــــــــــــــــــــ	<u></u> ′	

				LABOR	ATORY TEST DATA											
(AST	I C 136	)		ABRASION TEST (ASTH C 131)	SOUNDNE (ASTM	C 88)			GGREGA	C 127	AND C	128)	48441	#1 #0:1	ALK/ REACT (ASTM (	IVITY 🕴
NO. 30	NO. 50	NO. 100	NO. 200	PERCENT WEAR	PERCEN CA	T LOSS	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	CA	FA
	9.3	5.6	3.7	22.0	6.42	6.38		2.43		<b>V</b>		2.53				
	2.5	1.1	0.7	19.6	2.41	2.70					i	:				
33 <b>°</b>		14.7	10.7									2.62				
43.4		20.2	13.2									2.67				
44 <b>.</b>		7	3						}							
45.3°		22.7	16.7	:								2.66				
20 <b>°</b>		10	8									2.64				

FUE AME DRY LAKE, III

MX SI

6.55

2

FREGATE AVITY	ALK REACT (ASTM	AGGREGATE USE	
APPAR- ENT SEC	CA	FA	٧
			IIcr
		·	IIcr
			If/c
			Ic/f
			IIf
			IIf/c
			IIf
			IIf
			IIf/c

FUGRO NATIONAL FIELD STATION AND SUPPLEMENTARY TEST DATA DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

DEPARTMENT OF THE AIR FORCE - SMG

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - 900

TABLE
A-1
PAGE 7 OF 9

	-						
NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	BOULDERS AND/OR COBBLES PERCENT	BIST TAM THE
MAP						BOULDE AND/OR PERCEN	GRAYEL
89	DL-T-6	Dry Lake Valley	Aals	Silty Sand	SM		
90	DL-T-7	Dry Lake Valley	Aals	Silty Sand	SP-SM		
91	DL-T-8	Dry Lake Valley	Aafs	Silty Sand	SM		
92	MS-T-1	Muleshoe Valley	Aafs	Sandy Silt	ML		T
93	MS-T-2	Muleshoe Valley	Aals	Silty Sand	SM		0
94	MS-T-3	Muleshoe Valley	Aals	Sandy Silt	ML		T
95	MS-T-4	Muleshoe Valley	Aafs	Gravelly Sand	SM		30
96	MS-T-5	Muleshoe Valley	Aafs	Gravelly Sand	SP-SM		18
97	MS-T-6	Muleshoe Valley	Aals	Silty Sand	SM		20
98	P-T-2	Pahroc Valley	Aafs	Silty Sand	SM		5
99	P-T-4	Pahroc Valley	Aafs	Gravelly Sand	SM		20
100	P-T-6	Pahroc Valley	Aafs	Gravelly Sand	SP-SM		25
101	DM-T-2	Delamar Valley	Aafs	Sandy Gravel	GP		70
L	L	<u>L</u>	<u>L</u>	L		L	

			<del></del>	FIEL	.D OBSERV	ATIONS						<del></del>		-	
AND/OR COBBLES, Percent	DISTI MATE THA	RIBUTII RIAL F N COBB PERCEN	INER	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS		S	IEVE A	NALYSI	S, PER	CENT PA	SSING	(
AND/OR Percent	GRAVEL	SAND	FINES	PLAST	HARD	WEATH	MATERIALS	3 "	1½"	<b>¾"</b>	3/6 "	NO.	NO.	NO. 16	
										100	98	96.5	92*		72
			:						į	99	93.5	85	70.5		3
									100	87.3	75.3	65	57 <b>*</b>		4
	T	25	75												
	0	65	35											i	
	T	40	60				•								
ò	30	55	15												
	18	70	12								:				
	20	60	20												
	5	75	20												
	20	60	20												
	25	70	5												
	70	25	5						ļ						
															4

L	BO	RA	TN	RY	TFST	DATA	
		,,,,		11 1	1631	U 7 1 7	i i

INC	MT2A)	I C 136			ABRASION TEST ASTM C 131)	COUNDM	ESS TEST				C 127	AND C	128)			ALI	KAL
	. (1011		• /		ABRAS TEST ASTR C	(ASTW	C 88)			GGREGA				GREGAT		REACT (ASTM	C
	T	T	T	<del></del>	<del>                                     </del>		<del></del>	SPEC	IFIC G		E	SPEC	FIC GR	$\overline{}$			
0. 6	NO.	NO. 50	NO.	NO. 200	PERCENT	PERCEN	T LOSS	BULK	BULK	APPAR- ENT	PERCENT ABSORPTION	BULK	BULK SSD	APPAR- ENT	PERCENT 1850RPT10N	CA	
			+		WEAK.	LA	TA		330	-		}	330	ENI	-2		┼
	72.5		44	33										2.66			
	39 <b>*</b>	}	13	9	{			<u>{</u>	}					2.61			
	48.3		35.7	25.7	{ 			<u> </u>					, 1	2.66			
				 			   		<u> </u> 		<b>,</b>		}				
										{							
		i I															
}															}		
		ļ											) }				
	}			ļ	ţ			į	l	{					1		

DRY LA

DEPART

fü

Z Y	_ <u>6</u>	A Rea (Asti	LKALI Ctivity M C 289)	AGGREGATE USE
	PERCENT ABSORPTION	CA	FA	)9V
56				IIf
61				IIf
<b>6</b> 6				IIf/c
				IIIf
				IIIf
				IIIf
				IIf/c
				IIf
	i 			IIc/f

FUGRO MATIONAL FIELD STATION
AND SUPPLEMENTARY TEST DATA
DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - BMG

TABLE A-1 Page 8 of 9

VERO NATIONALING

P NUMBER	FIELD STATION	LOCATION	GEOLOGIC Unit	MATERIAL Description	USCS Symbol	BOULDERS AND/OR COBBLES, PERCENT	9 1
MAP						BOULDE AND/OR Percen	GRAVEL
102	DM-T-3	Delamar Valley	Aafs	Silty Sand	SP-SM		20
103	DM-T-4	Delamar Valley	Aafs	Gravelly Sand	SM		25
104	DM-T-5	Delamar Valley	Aafs	Silty Sand	SM		10
105	DM-T-6	Delamar Valley	Aafs	Gravelly Sand	SM		20
106	DM-T-7	Delamar Valley	Aolf	Sandy Silt	ML		0
107	DM-T-8	Delamar Valley	Aafs	Silty Sand	SM		5
108	DM-T-10	Delamar Valley	Aafs	Silty Gravel	GM		40

								1							
				FIEL	D OBSERVA	TIONS		ļ							
]	MATE THA	RIBUTII RIAL F N COBB PERCEN	INER Les.	PLASTICITY	HARDNESS	WEATHERING	DELETERIOUS		s	IEVE A	NALYSI	S, PER	CENT P	ASSING	(A
PERCENT	GRAVEL	SAND	FINES	PLAS	HARI	WEATH	MATERIALS	3"	1½"	<b>ኣ</b> "	3/8"	NO.	NO.	NO. 16	3
	20	70	10												
	25	60	15												and the state of the state of
	10	80	10												
	20	65	15										i		
	0	50	50												
	5	80	15												
	40	40	20												
					:										
			i											,	

1 1	100	104	TN	DV	TECT	DAT	
L	4 D U	IKA	יטוו	RΤ	TEST	UAI	A

DRY LA

DEPART

3

1011	ALM REACT (ASTM	AGGREGATE USE			
ABSORPTION	CA	FA	<		
			IIf		
			IIIf		
			IIf		
			IIc/f		
,					
!					
	!		<u> </u>		

FUGRO NATIONAL FIELD STATION
AND SUPPLEMENTARY TEST DATA
DRY LAKE, MULESHOE, DELAMAR, AND PANROC VALLEYS

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - 900

TABLE A-1 PAGE 8 OF

PARTHENT OF THE ATH FORCE - 180 PAGE 9 OF B

4


## EXPLANATION OF EXISTING DATA


Existing data pertaining to aggregates were extracted from the State of Nevada Department of Highways. These reports are compilations of avaiable site data from existing files and records and are intended to accurately locate, investigate, and catalog materials needed for highway construction. Explanations for column headings which appear in Table A-2, that have not been previously discussed in Table A-1, are given below:

Column Heading	Explanation							
Site Number	State of Nevada Department of Highways pit or site number. Locations correspond to map numbers listed on this table and placed on Drawing 1.							
Soundness Test	The testing of aggregates to determine their resistance to disintegration by saturated solutions of sodium sulfate. It furnishes information helpful in judging the soundness of aggregates subject to weathering action, particularly when adequate information is not available from service records of the material exposed to actual weathering							

conditions.

NUMBER	NUMBER			UNIT	MATERIAL	SYMBOL		
MAP NU	SITE N	DATA SOURCE	LOCATION	GEOLOGIC	DESCRIPTION	S SOSA	> 6"	3-6
109	LN15-1	Nevada Dept. of Highways	Pahranagat Valley	Au	Silty Gravel	GP-GM	5	11
110	LN 15-2	Nevada Dept. of Highways	Pahranagat Valley	Au	Silty Gravel	GM-GC	3	
111	LN15-3	Nevada Dept. of Highways	Pahranagat Valley	Au	Silty Gravel	GP-GM	Ħ	
112	LN 15-4	Nevada Dept. of Highways	Pahranagat Valley	Aol	Silty Gravel	GM-GC	#	
113	LN 15-7	Nevada Dept. of Highways	Pahranagat Valley	Au	Silty Gravel	GP-GM	4	
114	LN 15-8	Nevada Dept. of Highways	Pahranagat Valley	Aol	Silty Gravel	GP-GM	9	
115	LN 15-12	Nevada Dept. of Highways	Pahranagat Valley	Aol	Silty Gravel	GM	1	
116	LNRS-3	Nevada Dept. of Highways	Dry Lake Valley	Aolf	Silty Gravel	GP-GM	0	
117	LN24-2	Nevada Dept. of Highways	Delamar Mountains	Au	Clayey Gravel	GC	4	
118	LN02-5	Nevada Dept. of Highways	Pahranagat Valley	Aaf	Sandy Gravel	GP		10
119	LN02-7	Nevada Dept. of Highways	Pahranagat Valley	Au	Silty Gravel	GM		10
120	LN02-8	Nevada Dept. of Highways	Pahranagat Valley	Au	Sandy Gravel	GP		
121	LN02-9	Nevada Dept. of Highways	Pahranagat Valley	Au	Gravelly Sand	SP-SM		





SIEVE ANALYSIS										ABRASION TEST (ASTM C 131)	SOUNDNESS	(88 ) E					
3-6"	1ጷ"	1"	*"	<b>ኔ</b> "	<b>ኔ</b> ''	3/8"	NO.	ND.	NO.	NO.	NO.	NO.	NO.			T LOSS	SPE
	i .						4	10	16	40	50	100	200	PERCENT WEAR	CA	FA	BUL
10			26		· · · · · · · · · · · · · · · · · · ·	49							4–13	23.1			
4			19			35	:						5–26	25.4			
5			28			48							2–20	25.4			
4			16			31		į		i			5–11	28.3			
4			12			24							4-12	36.9			
9			30			45	i	į					5–12	25.5			
1			6			10							5–16	35	  - 		
1			11			29	i	I		ļ			7-22	25			
6			18			26							1–68	34.8			
100	92	84	77	62			48	68	49	20	15	9	6	22	6.42	6.38	
100	81	61	48	31		21	16	15	13	9	5	4	3	23		2.97	2.
		100	100	89		81	65	50	41	22	17	11	7	28.7	i		,
			100	85		74	62	48	38	20	16	11	7	31.2			

	SP	CIFIC (ASTM		Y AND	AI KALL PEACTIVE							
C	OARSE	AGGRE G/		F	INE AG	GREGAT	E	7 IN 423 (24)	ALKALI REACTIVITY			
SPECIFIC GRAVITY BULK BULK APPAR- SSD ENT				SPEC	IFIC G	RAVITY	E87	710	(ASTM C 289)			
BULK	SSD	APPAR- ENT	PERCABSOR	BULK	SSD	APPAR- ENT	PERCENT ABSORPTION	PLAST (AST AND	CA	FA		
		2.65		<u> </u> 				NP				
		2.56						NP-16				
		2.65						NP				
		2.58						NP-9				
		2.51						NP				
		2.68						NP				
								NP				
		2.52						NP				
		2.52						NP-17				
		2.53	}									
2.76	2.78	2.81	0.65									
		2.56						NP				
		2.59						NP				
				- [	Ì	1						

EXISTING TEST DATA
DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - 800

TABLE A-2 AGE 1 OF 1

UGRO NATIONAL ING.

APPENDIX B
Summary of Caliche Development

## DIAGNOSTIC CARGONATE MORPHOLOGY

STAGE		GRAVELLY SOILS	NONGRAVELLY SOILS					
1	Thin	, discontinuous pebbl	Few filaments or faint coatings					
п		tinuous pebble coating rpebble fillings	Few to at	oundant nodules, flakes,				
ш	Many	ninterpebble filling:	Many nodules and internodular fillings					
п	Lami hori	nar horizon overlying zon	Laminar horizon overlying plugged horizon					
:	STAGE	I Weak Ca	II Strong Ca	III K	II Indurated K			
•	GRAVELLY SOILS				K21m K22m K3			
1	NONGRAYELLY SO	ıııs Z			K2Im K22m			

Stages of development of a caliche profile with time. Stage I represents incipient carbonate accumulation, followed by continuous build-up of carbonate until, in Stage IV, the soil is completely plugged.


SUMMARY OF CALICHE DEVELOPMENT

Reference: Bile, L.W. Peterson, F.F., and Bressman, R.B., 1965, The K herizon: A master herizon of carbonate accumulation: Soil Science, v. 99, p. 74-92. MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - BMG

FIGURE B-1

WERO NATIONALING

APPENDIX C Unified Soil Classification System



From Wagner, 1957.

Shoundary chastifications. Soils possessing characteriates of two groups are designated by combinations of group symbols. For example GW-GC, well graded gravel-sand mixture with clay binder.

Plate Identifications on this chart are U.S. standard.

Field Identification for the Grahed Soils or Fractions

There procedures have to be performed on the minus No. 40 sieve size perricks, approximately 74, in. For field classification purposes, severaing is not intended. I Dry Surget (Coulting Counting ABLE

C-1

Florghary (Contistency near plants limit). No. 40 sizes size, a specience of Alter removing particle limit in the his body sizes size, a specience of a period of the first of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes of the sizes to the sizes of

simply remove by hand the coarse particles that interfere with the

UNIFIED SOIL CLASSIFICATION SYSTEM

MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE

## APPENDIX D

Dry Lake, Muleshoe, Delamar, and Pahroc Valleys Study Area Photographs



Older Lacustrine Deposit (Aolg), widely scattered within Pahranagat Valley, southwest of the Pahroc Valley area; Class I, coarse aggregate source (Field Station 30).

DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS STUDY AREA PHOTOGRAPH

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - BMO

7169RE

UGRO NATIONAL, INC.



Sandstone member of the Simonson Dolomite (Do) located within Pahroc Valley in the southwastern portion of the study area; Class I, crushed rock aggregate source (Field Station 35).

DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS STUDY AREA PHOTOGRAPH

MX SITING INVESTIGATION
DEPARTMENT OF THE AIR FORCE - SMG

71 CURE

<u>ugro national ino</u>

## APPENDIX E

Fugro National Geologic Unit Cross Reference

UARSA POTENTIAL SOURCE SYMBOLS


### AGGREGATE FUGRO NATIONAL GENERAL GEOLOGIC UNIT EXPLANATION


	<u></u>
	6K1
Ì	Shabo in regions their on a seasoned from tradity productions. Seasons then 18 percent come type in seasons and the those enters
Ì	effect for the least view the application of the trade of them.
{	Takingset up the consistency has high for $g=\frac{S_{1/g^{-1}}}{S_{1/g^{-1}}}$ for the consistency has subdivided the headings $\{0\}$
}	
Gr	[1] Introduce - Northing locks failed by solid- fication of no fee material banks in the surface
Yu	e g grante grandferte d'aire gapoits.  [15] Estion ve intermédate uni acidic. Foranic cots of intermédate and pointe d'appende de la del principal de la companyation forance de la companyation de la comp
Vb.	send cannot english material at a real the service service of the decision and service.  Serface to a conjunction and service decision and service.  The transfer material resolution of basic combinations.
[	osition generally termed by keller firetion of equitor materials at near the surface selg. basalts
Yu	of volcanningship e.g. asp. but recleas but. aggrowerster
Su	S SERIORISTAN LUMBIFFERENTIATED Races formed by accomplation of clastic years organic salids and or consider or pre-
Su, QTz	Completed minerals
	size particles a g sandstone orthodoxyntrile: er of cryptocryslatione strica e g apar chell
Ls, Do, Cau	imasiane delamite chata
}	S) Provinceous taces. Compassed of city and sold sized particles in g is instance carestone.
1	Sulfregor in Notes - Procedulated from solution at a result of separation in g. Theorem gapsum and entry size in successions.
1	S. Course Cracks of Sects - empayard of grant in test as
Mu	The transfer of the transfer o
Mu	
Mu	A parties and the parties of a parties of the parti
Mu	
QTz	Banacaprotes once farmed by meramorphics of rightly colored once of the colored of the colored once of the
	MSym-Fett
1	A 965:s-Fits gg905:11 Fines to coassengrained materials deposited print balls by endowater or gravity
Aal	Thunger this a Departs. Major modern stream
Au, Aal	thomas and tipographic deposits in Pigrated ferraces pardering odjan godfra dearhages
Au	A) to an Depair to . Wind-broom depair to bit same  Receiving as enther than Shedy's . Associated depairs.  Associated as
Aol	Re Plaza and Lacustrine Bedesits - Besetits accurring in auditing actives players - Re- or in either in accurring to the player or dependent of the players or dependent of the players or dependent of the players or dependent of the players of the
1	Sharetimes pass rated with estinct 1885 - An  An Browing Fan Benerits - Kitariel deposits consisting
Aat	at opports from and optor tool a liberale man developed from the from the professional state of the state of
Į	erum depositation shofting deposituation chambers neer the appin center. Tounger: Appin interestable
1	As and gider Asi a turius tans are exteren- tared by surface sert development, terrain conditions
Au	and present depositions of colonel entropement.  As the Bised war-recounts - Bost ordaily extensive unit is
	As (8s ) Perpendict out under res this senser of secriting
Aat	Magazia day


FUGRO NATIONAL GEOLOGIC UNIT CROSS REFERENCE


MX SITING INVESTIGATION DEPARTMENT OF THE AIR FORCE


FIGURE E-1









































0,







# EXPLANATION

## FUGRO NATIONAL FIELD STATIONS

BASIN-FILL UNITS (Potential Coarse and/or Fine Aggregates)

Data Stop, Sampled and Tested

O Data Stop

ROCK UNITS (Potential Crushed Rock Aggregates)

▲ Data Stop, Sampled and Tested

△ Bata Stop

#### EXISTING TEST DATA SITES

l Tast Data Available

Note: See Corresponding Map Number in Appendix A for Detailed Information

FUGRO NATIONAL FIELD STATION
AND EXISTING DATA SITE LOCATIONS
DRY LAKE, MULESHOE, DELAMAR, AND PAHROC VALLEYS


MX SITING INVESTIGATION


DEPARTMENT OF THE AIR FORCE - BMO


DRAWING


1


UGRO NATIONAL, INC.





















































20

Geologic Contact, Dashed Where Approximate

Approximate Concrete Aggregate and/or Road-Base Materials Source Boundary

Verification Study Area

# FUGRO NATIONAL VALLEY-SPECIFIC AGGREGATE RESOURCES SAMPLED AND TESTED FIELD STATIONS

BASIN-FILL AGGREGATE SAMPLE COARSE (c) AND FINE (f)	CRUSHED ROCK SAMPLE	CLASSIFICATION
	<b>A</b>	CLASS I
•	<b>^</b>	CLASS II
0	Δ	CLASS III

MGTE: SEE CORRESPONDING MAP NUMBER IN APPENDIX A FOR DETAILED INFORMATION

AGGREGATE RESOURCES MAP
DRY LAKE. MULESHOE. DELAMAR. AND PAHROC VALLEYS

MX SITING INVESTIGATION

DEPARTMENT OF THE AIR FORCE - BMO

DRAWING

2

UGRO NATIONAL, INC.

DAT

. .